

---

JOURNAL  
OF THE  
ARNOLD ARBORETUM

---

VOLUME 71

JULY 1990

NUMBER 3

---

THE GENERA OF CUPRESSACEAE  
(INCLUDING TAXODIACEAE) IN THE  
SOUTHEASTERN UNITED STATES<sup>1</sup>

JEFFREY A. HART<sup>2</sup> AND ROBERT A. PRICE<sup>3</sup>

CUPRESSACEAE Bartling, Ord. Nat. Pl. 90, 95. 1830,  
"Cupressinae," nom. cons.

(CYPRESS FAMILY)

Aromatic, resinous, evergreen or sometimes winter-deciduous, monoecious (or dioecious in *Juniperus* [and *Diselma*]) trees or shrubs. Bark fibrous and

<sup>1</sup>Prepared for the Generic Flora of the Southeastern United States, a long-term project made possible through the support of National Science Foundation Grants BSR-8415769 (C. E. Wood, Jr., principal investigator) and BSR-8716834 (N. G. Miller, principal investigator), under both of which this account was prepared. The 133rd in the series, this paper follows the format established in the first one (*Jour. Arnold Arb.* 39: 296-346, 1958) and continued to the present. The area covered by the Generic Flora includes North and South Carolina, Georgia, Florida, Tennessee, Alabama, Mississippi, Arkansas, and Louisiana. The descriptions are based primarily on the plants of this area, with information about extraregional members of a family or genus in brackets [ ]. The references that we have not verified are marked with asterisks.

We thank Carroll Wood and Norton Miller for the opportunities afforded by participation in the Generic Flora project and for their guidance in the study, and Rudolf Schmid for bibliographic assistance. Walter Judd and Richard Wunderlin provided useful information on the occurrence of *Callitris* in Florida. Library and herbarium collections at Harvard University and the University of California, Berkeley, were consulted in this study, and we wish to thank the staff at these institutions for their assistance. The illustration of *Chamaecyparis thuyoides* (based on plants collected in Norfolk Co., Massachusetts) was drawn by Karen Stoussenger under the direction of Carroll Wood, while that of *Juniperus* (based on cultivated plants from the University of California Botanical Garden, and *Demaree* 23779, *Krivda* 67-310, and *McCabe* 416, all at UC) was drawn by Linda Vorobik under the direction of Robert Price.

This paper is published in part as contribution number 640 from the New York State Science Service.

<sup>2</sup>1547 33rd Street, Sacramento, California 95816. Please address reprint requests % Dr. Norton Miller, Room 3132 CEC, New York State Education Department, Albany, New York 12230.

<sup>3</sup>Biological Survey, New York State Museum, The State Education Department, Albany, New York 12230. Current address: Biology Department, Indiana University, Bloomington, Indiana 47405.

separating into long strips or exfoliating in plates. Wood with axial parenchyma, lacking resin canals [sometimes with traumatic resin canals in *Sequoia* and related genera] and ray tracheids [reported only for *Chamaecyparis nootkatensis*]. Branches erect or spreading; branchlets erect to pendulous, terete or quadrangular, sometimes flattened in frondlike horizontal sprays (in Cupressaceae *s.s.*). Foliage leaves entire to minutely serrate, linear to linear-lanceolate and spirally arranged (often apparently 2-ranked by twisting of leaf bases) [or opposite in *Metasequoia*] in the traditional Taxodiaceae, or decussately opposite or in whorls of 3 [rarely 4] and scalelike or sometimes awl or needle shaped in the Cupressaceae *s. s.*; foliar resin canals 1 [to 3]. Pollen cones (microsporangiate strobili) sessile or short stalked, solitary or variously clustered, terminal on leafy branches or short shoots (or sometimes axillary); microsporophylls spirally arranged, decussately opposite, or ternate, ca. 6 to 24 per strobilus; microsporangia 2 to 10 per sporophyll, globose or ellipsoid, longitudinally dehiscent, pendulous, free, in 1 or 2 abaxial rows; pollen spheroidal, without saccae or prothallial cells; intine thick, exine with surface microverrucate, with papilla or obscure germinal aperture; male cells approximately equal in size. Ovulate cones solitary (sometimes secondarily clustered), subglobose to ovoid [to pyramidal], terminal or axillary, maturing in 1 to 3 seasons; bract and scale components largely fused in the mature cone, with bract tip protrusive or inconspicuous; bract-scale complexes spirally arranged or decussately opposite or ternate, each with 1 to 6 [to 10, or rarely to 20 in *Cupressus*] erect [or ultimately inverted], adaxial, bottle-shaped ovules; archegonia aggregated in terminal (or lateral) complexes; scales peltate or broadly ovate to triangular-ovate or oblong, thickened or strongly flattened at maturity, imbricate or valvate, [2 to 4] 6 to ca. 20 [to 40 or more] per cone, ultimately woody and separating (or fleshy and fused into a berrylike structure in *Juniperus*). Seeds 1 to several per scale, with [1 or] 2 (or 3) lateral [or nearly terminal] wings derived from the seed coat, or wingless; seed coat varying from thin to very thick and woody, often with resin ducts; cotyledons 2 to 6 (to 9 in *Taxodium*). Chromosome number usually  $2n = 22$  (occasionally 33, 44 [66 in *Sequoia sempervirens*]). (Including Taxodiaceae Warming, Haandb. Syst. Bot. ed. 2. 163. 1884; Juniperaceae Schaffner.) TYPE GENUS: *Cupressus* L.

A family of 29 genera<sup>4</sup> and approximately 130 to 140 species concentrated in the temperate portions of the Northern and Southern hemispheres, but with some species in boreal and austral areas and with *Juniperus procera* Hochst. extending into tropical montane areas of eastern Africa. Of the eight genera native in North America, *Chamaecyparis* Spach, *Juniperus* L., *Taxodium* Rich., and *Thuja* L. occur in the southeastern United States, while *Calocedrus* Kurz, *Cupressus* L., *Sequoia* Endl., and *Sequoiadendron* Buchh. occur only in the western part of the continent. About 16 of the genera are monotypic, although several of these had much larger ranges (and presumably greater numbers of species) in the Tertiary than they do now (Florin, 1963). The largest and most

<sup>4</sup>Or fewer, if one treats *Libocedrus* Endl. in the broad sense, including some or all of the segregate genera *Austrocedrus* Florin & Boutelje, *Papuacedrus* H. L. Li, and *Pilgerodendron* Florin, as was variously done by De Laubenfels (1972, 1988) and Eckenwalder (1976).

widespread genera are *Juniperus* (50 or more species) and *Cupressus* (perhaps 13 species) in the Northern Hemisphere, and *Callitris* Vent. (ca. 15 species) in the Southern Hemisphere.

Most recent treatments of the conifers have followed Pilger in recognizing seven families, with the Cupressaceae separate from the Taxodiaceae. However, many European authors (including Emberger, H. Erdtman & Norin, and Lebreton) have united these two families in the order Cupressales, and a number of authors (Eckenwalder; Hart; Price & Lowenstein) have advocated merging the two families under the earlier name Cupressaceae, as is done here. Although Pilger and subsequent authors have circumscribed families primarily on the basis of reproductive characters, especially those of the ovulate cone, the Cupressaceae and Taxodiaceae are similar in development and morphology of the bract-scale complexes (Florin, 1951) and differ primarily in phyllotaxy of leaves and cone scales. The leaves of the Cupressaceae *s.s.* are decussately opposite or whorled, while those of the Taxodiaceae are alternate (except in *Metasequoia* Miki ex Hu & Cheng, in which they are decussately opposite). The shift from spiral to decussate arrangement is hardly unique to the Cupressaceae *s.l.* Both patterns are also seen in the Taxaceae (where *Amentotaxus* Pilger has opposite leaves) and the Podocarpaceae (where *Microcachrys* J. D. Hooker has opposite leaves). The taxodiaceous genera also differ from the Cupressaceae *s.s.* in having a papilla protruding from the germinal area of the pollen grain, although this can be very obscure in some genera (G. Erdtman; Ueno, 1960a).

The two families are held together by an impressive number of morphological characters, including derived features of embryology (archegonia borne in complexes; free-nuclear mitotic divisions three or fewer in proembryogeny), palynology (pollen grains nonsaccate, lacking prothallial cells), chromosome base number ( $x = 11$ ), and high degree of bract-scale fusion in the ovulate cone. Most genera have seeds with lateral wings derived from the seed coat (Singh, 1978), ovules are often more than two per cone scale, and microsporangia are usually more than two per sporophyll. Preliminary cladistic analyses of morphological characters (Hart) and immunological comparisons of seed proteins (Price & Lowenstein) indicate that the Cupressaceae *s.l.* are a natural group quite distinct from the other families of conifers and that the Cupressaceae *s.s.* form a monophyletic group apparently derived from within the traditional Taxodiaceae.

The Cupressaceae *s.l.* appear to be only distantly related to the other extant groups of conifers except for the monotypic *Sciadopitys* Sieb. & Zucc., Japanese umbrella pine, which has often been treated as a morphologically isolated member of the Taxodiaceae (see Eckenwalder; Liu & Su; Pilger; Sporne) or as the separate family Sciadopityaceae Hayata (Doyle & Brennan, 1971; Hart; Price & Lowenstein; Schlarbaum & Tsuchiya, 1985). *Sciadopitys* is similar to the Cupressaceae *s.l.* in having ovulate cones with substantial bract-scale fusion and several seeds per cone scale, each with two lateral wings derived from the seed coat, and nonsaccate pollen grains lacking prothallial cells. Its chromosome base number ( $x = 10$ ) is apparently derived from that of the Cupressaceae *s.l.* by aneuploid reduction (Schlarbaum & Tsuchiya, 1985). It is unique among

conifers in having elongate "double needles"—axillary short shoots that combine features of leaf and stem in their development and morphology (Roth)—as its photosynthetic organs. It retains primitive states for embryological characters (archegonia not grouped in complexes, five sets of free-nuclear mitoses in proembryogeny—Dogra, 1980; Doyle, 1963; Liu & Su; Tahara, 1937, 1940), the derived states of which are shared by the Cupressaceae *s.l.*; it also differs in having male cells unequal in size (Tahara, 1940), pollen grains with much more prominent verrucate sculpture (Ho & Sziklai), and wood without axial parenchyma and with much larger cross-field pits (Phillips). *Sciadopitys* is very distant from the Cupressaceae *s.l.* in immunological comparisons of seed proteins (Price & Lowenstein), and it also has a long fossil record, dating back at least to the Jurassic (Florin, 1922, 1963; Manum). Thus it appears to be a well-separated sister-group of the Cupressaceae *s.l.* (Hart; Price & Lowenstein), and we treat it as the monotypic family Sciadopityaceae.

Most modern tribal and subfamilial classifications of the Cupressaceae/Taxodiaceae lineage have been devised in the context of two separate families, the Cupressaceae and the Taxodiaceae, or equivalent groups of lower rank (see, for example, Gaussen, 1967, 1968; Pilger; Pilger & Melchior; Vierhapper). The Cupressaceae *s.s.* have been divided into tribes or subfamilies in a variety of ways (compare Endlicher; Gaussen, 1968; Janchen; H. L. Li, 1953a; Moseley; Pilger). In perhaps the most widely utilized modern treatment, H. L. Li (1953a) divided the group into two subfamilies: Cupressoideae, with nine genera in the Northern Hemisphere (further divided into tribes Cupresseae, Junipereae Neger, and Thujopsidae Endl.), and Callitroideae Saxton, including the ten Southern Hemisphere genera plus *Tetraclinis* Masters in Spain and northern Africa (further divided into tribes Actinostroboeae Endl., Libocedreae H. L. Li, and Tetraclineae H. L. Li). The cupressoid genera were separated from the callitroid genera as having imbricate rather than valvate scales on the mature ovulate cones. However, the lowermost cone scales are often similar in arrangement in both groups, as was noted by De Laubenfels (1965). Moreover, the mature cone scales of *Cupressus* are nonoverlapping. The cones of the two subfamilies mostly differ in the reduced axis and usually fewer cone scales in the callitroid genera. The whorls of cone scales may be partially overlapping at the time of pollination in the Southern Hemisphere genera but come to lie at approximately the same level in the mature cone, rather than being separated along the cone axis. Reduction in cone-scale number has also occurred in several Northern Hemisphere genera (e.g., in *Microbiota* Komarov, with only two to four cone scales on a reduced axis (Krüssmann; Rushforth), in *Calocedrus*, and within *Chamaecyparis* and *Juniperus*). The presence of derived features of embryology (laterally positioned archegonial complexes and reduction of the number of free-nuclear divisions in the early proembryo) appears to support a close relationship among at least some of the Southern Hemisphere genera (*Callitris*, *Actinostrobus* Miq., and *Widdringtonia* Endl.—Dogra, 1984; Doyle & Brennan, 1972; Singh), although sampling has been very limited, and many of these genera have never been studied.

Other classifications have associated *Libocedrus* and its segregate genera with the thujoid genera of the Northern Hemisphere, which share elongate cone



scales and flattened ultimate branch systems (De Laubenfels, 1953, 1988; Janchen; Pilger; Vierhapper). However, the northern genera appear to differ in wood anatomy (Boutelje; Peirce, 1937). Distribution of tropolone and biflavonoid compounds (H. Erdtman & Norin; Gadek & Quinn, 1985), and preliminary data on anatomical characters such as details of pitting of the foliar transfusion tracheids (Gadek & Quinn, 1988) only partially agree with H. L. Li's (1953a) classification. Thus several recent authors (De Laubenfels, 1988; Gadek & Quinn, 1985, 1988) have questioned whether Li's subfamilies are natural groups, and additional morphological and macromolecular comparisons will be necessary to resolve their phylogenetic relationships.

The nine taxodiaceous genera (with *Sciadopitys* excluded) comprise only about 12 or 13 species and represent remnants of a group that was larger and more widespread in the Mesozoic and Tertiary (Florin, 1963; Miller, 1977, 1988). Many of the extant genera had wider geographic distributions in the past, as is indicated by the fossil record, and several occur back to the Cretaceous. One genus *Athrotaxis* D. Don, is now endemic to Tasmania, five (*Cryptomeria* D. Don, *Cunninghamia* R. Br., *Glyptostrobus* Endl., *Metasequoia*, and *Taiwania* Hayata) to eastern Asia, and three (*Sequoia*, *Sequoiadendron*, and *Taxodium*) to North or Central America.

Classifications of the Taxodiaceae have tended to emphasize form and development of the bract-scale complexes in the ovulate cone, but there are a number of differences in the details of the treatments (see Eckenwalder; Gausson, 1967; Hida, 1957, 1962; Janchen; Liu & Su; Pilger & Melchior; Vierhapper), and a rigorous tribal or subfamilial treatment seems premature. Most authors group *Sequoia* with *Sequoiadendron* and *Taxodium* with *Glyptostrobus*, and recent researchers (Eckenwalder; Gausson, 1967; Miller, 1988; Miller & Crabtree) have emphasized the similarities of *Athrotaxis*, *Cunninghamia*, and *Taiwania*. Preliminary cladistic analysis of a broader set of characters (Hart) and immunological comparison of seed proteins (Price & Lowenstein; Price, unpublished data) tend to support the groupings noted above, but place *Athrotaxis* in a more isolated position. These analyses differ primarily in the placement of *Metasequoia* and *Cryptomeria* relative to the other genera, associating *Metasequoia* with the other winter-deciduous genera *Glyptostrobus* and *Taxodium* (Hart) or with *Sequoia* and *Sequoiadendron* (Price & Lowenstein), and *Cryptomeria* with *Taiwania* and *Cunninghamia* (Hart) or with *Glyptostrobus* and *Taxodium* (Price & Lowenstein).

Chromosome numbers are often very stable within families of conifers (Ehrendorfer; Khoshoo, 1961), in marked contrast to the situation in the angiosperms. With the removal of *Sciadopitys* to its own family, the genera of Cupressaceae *s.l.* are apparently all characterized by a base number of  $x = 11$ .<sup>5</sup> Counts have been obtained for all species of the nine taxodiaceous genera and for species of 16 of the cupressaceous genera, including all ten Northern Hemisphere ones (see particularly Hair; Khoshoo, 1961; L.-C. Li; Mehra & Khoshoo; Sax & Sax). The great majority of the species have the diploid number  $2n =$

<sup>5</sup>*Fokienia hodginsii* (Dunn) Henry & Thomas has been reported by Chen to have a chromosome number of  $2n = 24$ , but L.-C. Li & Hu have more recently obtained  $2n = 22$  for the species.

22. Two monotypic genera are polyploid: *Sequoia sempervirens* (Lamb.) Endl. is a hexaploid with  $2n = 66$ , while *Fitzroya cupressoides* (Molina) Johnston has been reported by Hair to have  $2n = 44$ . Triploid or tetraploid counts have been obtained for forms (primarily cultivated) of several species of *Juniperus* and also for occasional variants of the otherwise diploid *Cryptomeria japonica* (L. f.) D. Don and *Chamaecyparis pisifera* (Sieb. & Zucc.) Endl. Karyotypic comparisons of the taxodiaceous genera were reviewed by Schlarbaum & Tsuchiya (1984), who noted some differences in arm lengths and ratios and presence or position of secondary constrictions. *Cunninghamia* and *Taiwania* differ from the other taxodiaceous genera in having more diversity in chromosome size and a greater number of submetacentric (vs. metacentric) chromosomes, in agreement with the relationship between these genera indicated by their similarity in cone-scale development (Hida, 1957; Liu & Su).

The Cupressaceae *s.l.* are unusual among the conifers in having archegonia grouped tightly in complexes, usually with a well-defined jacket layer (Dogra, 1984; Liu & Su; Singh). The archegonial complexes are usually located near the micropyle, but are positioned along the sides of the gametophyte in at least some of the Southern Hemisphere genera of Cupressaceae *s.s.* (*Actinostrobus*, *Callitris*, and *Widdringtonia*—see Doyle & Brennan, 1972; Singh) and in *Sequoia* and *Sequoiadendron* (Liu & Su) and toward the chalazal end in *Athrotaxis* (Brennan & Doyle). There are three sets of free-nuclear mitoses in the proembryogeny of most genera, but the number is reduced to two in *Athrotaxis* and *Callitris* (and probably *Actinostrobus* and *Widdringtonia*). Wall formation accompanies the first mitotic division in *Sequoia*, a very unusual feature among the conifers (Singh). Cleavage polyembryony of various types occurs as a regular part of development in most genera of the Cupressaceae *s.l.* except for *Athrotaxis*, *Thuja*, and *Thujopsis*, in which it occurs only sporadically (Dogra, 1984; Doyle & Brennan, 1971, 1972).

The Cupressaceae are wind pollinated, as are the other conifers, and have a pollination-drop mechanism of pollen capture, which is seen in most other gymnosperms and is evidently the primitive state among the conifers (see Doyle, 1945; Singh). Dispersal of the seeds is usually by wind or gravity, except in *Juniperus*, where the fleshy cones are eaten by birds or mammals, and *Taxodium*, where the thickened seed coat may aid in distribution by water (Fowells).

Many taxodiaceous and cupressaceous genera have been shown to have vesicular-arbuscular mycorrhizae and to lack root nodules, while *Sciadopitys* is more similar to the Podocarpaceae and Araucariaceae in having root nodules (Khan & Valder).

Chemical studies have been conducted on wood and leaves of many of the genera of Cupressaceae *s.l.*, with greatest emphasis on the Northern Hemisphere and Australian groups (see reviews in H. Erdtman & Norin; Hegnauer, 1962, 1986). Biflavonoid composition has been studied in virtually all of the genera worldwide (Gadck & Quinn, 1983, 1985; Geiger & Quinn, 1975, 1982). Compounds of the amentoflavone and hinokiflavone series are widespread among gymnosperms generally and have been found in most genera of the family, although the latter series is apparently absent in the Australian genera *Callitris*

and *Actinostrobus* (Gadek & Quinn, 1983). The cupressuflavone series is of more limited distribution, occurring in the Araucariaceae, one genus of the Podocarpaceae (*Lepidothamnus* Phil.), and portions of the Cupressaceae *s.s.* (Gadek & Quinn, 1985; Geiger & Quinn, 1982). Cupressuflavone is a major component in *Calocedrus*, *Cupressus*, *Juniperus*, and *Tetraclinis*, and a lesser one in *Platycladus* Spach and individual species of *Chamaecyparis* and *Thuja* (but not others), all of these indigenous to the Northern Hemisphere. Taiwaniaflavone, an unusual biapigenin biflavoid found only in *Taiwania*, *Calocedrus*, and *Neocallitropsis* Florin, is probably a convergent feature, since the three genera are very dissimilar in morphology.

The cytotoxic lignans podophyllotoxin and/or desoxypodophyllotoxin, which have been used in both traditional and modern medicine as antitumor agents, are found in the leaves of a variety of cupressaceous genera, including *Austrocedrus*, *Callitris*, *Calocedrus*, *Chamaecyparis*, *Juniperus*, and *Thujopsis* (Cairnes *et al.*; H. Erdtman & Norin; Hegnauer, 1986). The related but noncytotoxic compound savinin is present in the wood of several species of *Juniperus* and also in *Taiwania* (H. Erdtman & Norin; Hegnauer, 1986).

Diverse terpene compounds are found in the wood, leaves, and other plant parts of the Cupressaceae *s.l.* and are responsible for much of the aromatic nature of the plants. Most of the monoterpene compounds in the Cupressaceae *s.l.* occur widely in other conifers, while sesquiterpenes of the cedrane, thujopsane, widdrane, and cuparane types are particularly characteristic of the Northern Hemisphere genera of Cupressaceae *s.s.* and also of *Widdringtonia* (H. Erdtman & Norin). Several of these compounds have recently been reported to occur in low concentration in the foliar resin of *Cryptomeria* (Yatagai & Sato), and detailed studies may find them to be more widely distributed among the taxodiaceous genera.

Tropolones structurally related to the terpenes are important heartwood components of several genera of the Cupressaceae *s.s.*, particularly those of the Northern Hemisphere. These compounds, notable for their fungicidal activity, are apparently absent from the other conifers (H. Erdtman & Norin; Hegnauer, 1986). Tropolones are characteristic of *Calocedrus*, *Cupressus*, *Platycladus*, *Tetraclinis*, *Thuja*, *Thujopsis*, and most but not all species of *Chamaecyparis* and *Juniperus* (H. Erdtman & Norin). They are found in *Austrocedrus* and the related *Papuacedrus* but are apparently absent in the other Southern Hemisphere genera.

Alkaloids are relatively uncommon components in the conifers and in the Cupressaceae *s.l.* are well documented only for *Athrotaxis*, all species of which contain homoerythrinane compounds (Hegnauer, 1986, 1988).

Many genera of Cupressaceae *s.l.*, especially species of *Chamaecyparis*, *Cryptomeria*, *Cupressus*, *Juniperus*, *Metasequoia*, *Platycladus*, *Sequoia*, and *Thuja*, are important as ornamental trees or shrubs (L. H. Bailey; Bean; Dallimore & Jackson; Ouden & Boom; Krüssmann). *Sequoia* and *Sequoiadendron* are among the largest trees in the world and are centers of attraction in several national and state parks in California. Wood of many genera of Cupressaceae *s.l.* is resistant to insect and fungal attack and thus has been highly sought for uses requiring durability. Wood of various species of *Juniperus*, *Thuja*, and *Cha-*

*maccyparis* has been important for shingles, and that of *Sequoia* for outdoor uses such as decks and fences.

## REFERENCES:

- AASE, H. C. Vascular anatomy of the megasporophylls of conifers. *Bot. Gaz.* **60**: 277–313. 1915.
- ALOSI, M. C., & R. B. PARK. A survey of phloem polypeptides in conifers. *Curr. Topics Pl. Biochem. Physiol.* **2**: 250. 1983. [Several genera of Cupressaceae *s.l.* show a distinct pattern differing from those in *Sciadopitys* and in the other conifer families.]
- ALVIN, K. L., & M. C. BOULTER. A controlled method of comparative study for taxodiaceous leaf cuticles. *Bot. Jour. Linn. Soc.* **69**: 277–286. *pls. 1–5*. 1974. [SEM comparisons of *Athrotaxis*, *Cryptomeria*, *Cunninghamia*, *Glyptostrobus*, *Sequoia*, *Sequoiadendron*, and *Taxodium*.]
- BAILEY, L. H. The cultivated conifers in North America. 404 pp. *158 pls.* New York. 1933.
- BAILEY, N. Know your wood: cedar. *Wood Working Dig.* **53**: 85–89. 1951.\* [*Calocedrus*, *Chamaecyparis*, *Juniperus*, *Thuja*.]
- BAILLON, H. Conifères. *Hist. Pl.* **12**: 1–45. 1894. [Cupressaceae, 4–11, 26, 29, 30, 34–40.]
- BANTHORPE, D. V., H. F. S. DAVIES, C. GATFORD, & S. R. WILLIAMS. Monoterpene patterns in *Juniperus* and *Thuja* species. *Pl. Mcd.* **23**: 64–69. 1973. [*Juniperus chinensis*, *J. communis*, *J. horizontalis*, *J. oxycedrus*, *J. phoenicea*, *J. Sabina*, *J. scopulorum*, *Platycladus orientalis*, *Thuja occidentalis*, *T. plicata*, *T. Standishii*.]
- BARTHLOMEW, B., D. E. BOUFFORD, & S. A. SPONGBERG. *Metasequoia glyptostroboides*—its present status in central China. *Jour. Arnold Arb.* **64**: 105–128. 1983. [History of discovery of the dawn redwood, and its status as of 1980.]
- BEAN, W. J. Trees and shrubs hardy in the British Isles. ed. 8. 4 vols. London. 1970–1980. [*Chamaecyparis*, **1**: 591–601. 1970; *Juniperus*, **2**: 478–498. 1973; *Taxodium*, **4**: 557–560. 1980; *Thuja*, **4**: 577–586. 1980; also treated are *Cryptomeria*, *Cupressus*, *Glyptostrobus*, *Libocedrus* (here including *Austrocedrus* and *Calocedrus*), *Metasequoia*, *Sequoia*, *Sequoiadendron*, and *Thujopsis*.]
- BENTHAM, G., & J. D. HOOKER. *Gen. Pl.* **3**(1): 424–430. 1880. [Cupressaceae *s.l.*]
- BOUTELJE, J. B. The wood anatomy of *Libocedrus* Endl., *s. lat.*, and *Fitzroya* J. D. Hook. *Acta Horti Berg.* **17**: 177–216. *pls. 1–8*. 1955.
- BRENNAN, M., & J. DOYLE. The gametophytes and embryogeny of *Athrotaxis*. *Sci. Proc. Roy. Dublin Soc.* **11**: 27: 193–252. 1956.
- BRITTON, N. L. North American trees. x + 894 pp. New York. 1908. [Cupressaceae, 86–121; illustrations.]
- . The swamp cypresses. *Jour. New York Bot. Gard.* **27**: 205–207. 1926. [*Glyptostrobus*, *Taxodium*.]
- BUCHHOLZ, J. T. The embryogeny of *Sequoia sempervirens* with a comparison of the sequoias. *Am. Jour. Bot.* **26**: 248–256. 1939a.
- . The generic segregation of the sequoias. *Ibid.* 535–538. 1939b. [*Sequoiadendron* distinguished from *Sequoia*.]
- . Generic and subgeneric distribution of the Coniferales. *Bot. Gaz.* **110**: 80–91. 1948.
- BUTTS, D., & J. T. BUCHHOLZ. Cotyledon number in conifers. *Trans. Illinois Acad. Sci.* **33**: 58–62. 1940. [Original counts and literature summary, including most genera of the Cupressaceae *s.l.*]
- CAIRNES, D. A., D. G. I. KINGSTON, & M. MADHUSUDANA RAO. High performance liquid chromatography of podophyllotoxins and related lignans. *Jour. Nat. Prod.* **44**: 34–37. 1981. [Occurrence in species of *Austrocedrus*, *Callitris*, *Calocedrus*, and *Juniperus*.]

- CAMPO-DUPLAN, M. VAN. Recherches sur la phylogénie des Taxodiacées d'après leurs grains de pollen. Trav. Lab. Forest. Toulouse, Tome II, Sect. I, Vol. IV, Art. II: 10-14. 1951.
- . Recherches sur la phylogénie des Cupressacées d'après leurs grains de pollen. *Ibid.*, Art. III: 1-20. 1953.
- CARRIÈRE, E. A. Traité général des conifères. ed. 2. xii + 910 pp. Paris. 1867. [Cupressinées, including Taxodiaceae, 1-236.]
- CHAMBERLAIN, C. J. Gymnosperms: structure and evolution. xi + 484 pp. Chicago. 1935.
- CHANEY, R. W. Redwoods—occidentale and orientale. Science 110: 551, 552. 1949. [*Metasequoia*, *Sequoia*, *Sequoiadendron*.]
- . A revision of fossil *Sequoia* and *Taxodium* in western North America based on the recent discovery of *Metasequoia*. Trans. Am. Philos. Soc. II, 40: 169-263. 1951.
- CHANG, Y.-P. Bark structure of North American conifers. U. S. Dep. Agr. Tech. Bull. 1095. ii + 86 pp. 1954. [Cupressaceae, 47-67, figs. 29-37; includes *Calocedrus*, *Chamaecyparis*, *Cupressus*, *Juniperus*, *Sequoia*, *Taxodium*, *Thuja*.]
- CHEN, K.-Y. Chromosome number of *Fokienia*. (In Chinese; English summary.) Acta Bot. Sinica 25: 120-122. 1983. [Count of  $2n = 24$  obtained for *F. Hodginsii*; needs confirmation.]
- CHEN, Z.-K., & F.-H. WANG. Development of gametophytes in *Fokienia* (Cupressaceae). (In Chinese; English summary.) Acta Bot. Sinica 22: 6-10. 1980a.
- & ———. Studies in fertilization of *Fokienia*. *Ibid.* 22: 221-226. 1980b.
- & ———. The early embryogeny of the genus *Fokienia*, with a note on its systematic position. Acta Phytotax. Sinica 19: 23-28, pls. 1, 2. 1981.
- CHENG, W.-C., & L.-K. FU, eds. Gymnospermae. (In Chinese; nomenclatural portions primarily in English and Latin.) Fl. Reipubl. Pop. Sinicae 7. xiv + 544 pp. 1978. [Cupressaceae *s.l.*, 281-398; many illustrations.]
- CHOWDHURY, C. R. The embryogeny of conifers: a review. Phytomorphology 12: 313-338. 1962.
- CLIFFORD, H. T., & J. CONSTANTINE. Ferns, fern allies, and conifers of Australia. 150 pp. St. Lucia, Queensland. 1980. [Keys and descriptions for *Actinostrobus*, *Athrotaxis*, *Callitris*, *Diselma*.]
- COKER, W. C., & H. R. TOTTEN. Trees of the Southeastern States. ed. 3. viii + 419 pp. 7 pls. Chapel Hill. 1945. [Cupressaceae *s.l.*, 42-52.]
- COLTMAN-ROGERS, C. Conifers and their characteristics. 334 pp. London. 1920.
- CONKLE, M. T. Electrophoretic analysis of variation in native Monterey cypress (*Cupressus macrocarpa* Hartw.). Pp. 249-256 in T. S. ELIAS, ed., Conservation and management of rare and endangered plants. 1987. [Electrophoretic variation is substantial despite current very restricted geographic distribution.]
- COULTER, J. M., & C. J. CHAMBERLAIN. Morphology of gymnosperms. ed. 2. xi + 466 pp. Chicago. 1917.
- DAGUILLON, A. Observations morphologiques sur les feuilles des Cupressinées. Rev. Gén. Bot. 11: 168-204, pl. 5. 1899. [Including *Chamaecyparis*, *Cryptomeria*, *Cupressus*, *Juniperus*, *Platycladus*, *Sequoia*, *Sequoiadendron*, *Taxodium*, *Thuja*.]
- DALLIMORE, W., & A. B. JACKSON. A handbook of Coniferae and Ginkgoaceae. ed. 4, revised by S. G. HARRISON. xix + 729 pp. 46 pls. London. 1966.
- DARK, S. O. S. Chromosomes of *Taxus*, *Sequoia*, *Cryptomeria*, and *Thuja*. Ann. Bot. 46: 965-977. 1932.
- DE LAUBENFELS, D. J. The external morphology of coniferous leaves. Phytomorphology 3: 1-20. 1953.
- . The relationships of *Fit-roya cupressoides* (Molina) Johnston and *Diselma Archeri* J. D. Hooker based on morphological considerations. *Ibid.* 15: 414-419. 1965. [Relationships among genera of Cupressaceae and Taxodiaceae discussed.]

- . Cupressaceae. In: A. AUBREVILLE & J.-F. LEROY, eds. *Fl. Nouvelle Calédonie et Dépendances* 4: 144–164. 1972. [*Calliris*, *Libocedrus*, *Neocallitropsis*.]
- . Coniferales. *Fl. Males.* 1. 10(3): 337–453. 1988. [Cupressaceae, 444–447; *Libocedrus*, including *Papuacedrus*.]
- DLUHOSCH, H. Die Blüten der Coniferen. III. Entwicklungsgeschichtliche Untersuchungen über die Mikrosporophyllgestaltung der Coniferen. *Bibliot. Bot.* 114(3): 1–24. pls. 1–7. 1936. [Cupressaceae, 9–17, pls. 3–7.]
- DOAK, C. C. Multiple male cells in *Cupressus arizonica*. *Bot. Gaz.* 94: 168–182. 1932.
- . Morphology of *Cupressus arizonica* gametophytes and embryogeny. *Ibid.* 98: 808–815. 1937.
- DOGRA, P. D. Embryogeny of the Taxodiaceae. *Phytomorphology* 16: 125–141. 1966.
- . Embryogeny of gymnosperms and taxonomy—an assessment. *Glimpses Pl. Res.* 5: 114–128. 1980. [Embryogeny is reasonably consistent with the proposed merger of the Cupressaceae and the Taxodiaceae.]
- . The embryology, breeding systems, and seed sterility in Cupressaceae—a monograph. *Ibid.* 6: 1–113. figs. 1–264. 1984.
- DOYLE, J. Developmental lines in pollination mechanisms in the Coniferales. *Sci. Proc. Roy. Dublin Soc.* 24: 43–62. 1945.
- . Proembryogeny in *Pinus* in relation to that in other conifers—a survey. *Proc. Irish Acad. B.* 62: 181–216. 1963.
- & M. BRENNAN. Cleavage polyembryony in conifers and taxads—a survey. I. Podocarps, taxads & taxodioids. *Sci. Proc. Roy. Dublin Soc. A.* 4: 57–88. 1971; II. Cupressaceae, Pinaceae and conclusions. *Ibid.* 137–158. 1972.
- & W. T. SAXTON. Contribution to the life history of *Fitzroya*. *Proc. Irish Acad. B.* 41: 191–217. 1933.
- DUHOUX, E. Mechanism of exine rupture in hydrated taxoid type of pollen. *Grana* 21: 1–7. 1982. [*Cupressus arizonica*, *Juniperus communis*.]
- DUNCAN, W. H., & M. B. DUNCAN. Trees of the southeastern United States. xi + 322 pp. Athens, Georgia, and London. 1988. [Cupressaceae *s.l.*, 40–44, 123, 124; *color pls.*, maps of the southeastern species; *Cunninghamia lanceolata* reported as cultivated and potentially escaping in the Southeast.]
- ECKENWALDER, J. A. Re-evaluation of Cupressaceae and Taxodiaceae: a proposed merger. *Madroño* 23: 237–256. 1976. [Morphological characters tabulated for families of conifers and genera of Cupressaceae *s.l.*; taxa compared using indices of similarity; tentative classification offered for the combined family.]
- EHRENDORFER, F. Evolutionary significance of chromosomal differentiation patterns in gymnosperms and primitive angiosperms. Pp. 220–240 in C. BECK, ed., *Origin and early evolution of angiosperms*. New York. 1976.
- EICHLER, A. W. Coniferae. In: A. ENGLER & K. PRANTL, *Nat. Pflanzenfam.* II. 1: 28–116. 1889. [With contributions by ENGLER & PRANTL.]
- EMBERGER, L. Gymnospermes. *Traité de botanique systématique* 2(1): 383–459. 1960. [Cupressales, including Cupressaceae and Taxodiaceae, 434–448.]
- ENDLICHER, S. L. *Synopsis coniferarum.* iv + 368 pp. St. Gall, Switzerland. 1847.
- ERDTMAN, G. Pollen and spore morphology/plant taxonomy. Vol. 2. Gymnospermae, Pteridophyta and Bryophyta (illustrations). *Frontisp.* + iv + 151 pp. 5 pls. Stockholm. 1957. Vol. 3. Gymnospermae, Bryophyta (text). 191 pp. 24 pls. Stockholm. 1965.
- ERDTMAN, H., & T. NORIN. The chemistry of the order Cupressales. *Fortschr. Chem. Organ. Naturstoffe* 24: 206–287. 1966. [Important review of chemistry of Cupressaceae and Taxodiaceae.]
- FERRÉ, Y. DE. Cotylédons et évolution chez les Cupressinées. *Bull. Soc. Hist. Nat. Toulouse* 77: 71–83. 1942.
- . L'évolution parallèle des Taxodinécs et des Abietinécs. *Ibid.* 78: 71–83. 1943.
- . Cotylédons et évolution chez les Taxodinécs. *Ibid.* 82: 214–224. 1947.

- & H. GAUSSEN. Les Cupressacées australes. *Compt. Rend. Acad. Sci. Paris* **267**: 483–487. 1968.\*
- , M. L. ROUANE, & P. WOLTZ. Systématique et anatomie comparée des feuilles de Taxaceae, Podocarpaceae, Cupressaceae de Nouvelle-Calédonie. *Cahiers Pacifique* **20**: 241–266. 1978. [*Libocedrus*, *Neocallitropsis*.]
- FINS, L., & W. J. LIBBY. Population variation in *Sequoiadendron*: seed and seedling studies, vegetative propagation, and isozyme variation. *Silvae Genet.* **31**: 101–148. 1982.
- FITSCHEN, J. Handbuch der Nadelholzkunde. xv + 765 pp. Berlin. 1930. [Revised ed. 3 of BEISSNER's Handbuch der Nadelholzkunde.]
- FITTING, H. Über die Induktion der Dorsiventralität in den blattähnlichen Zweigsystemen von Cupressaceen. *Jahrb. Wiss. Bot.* **90**: 417–463. 1942. [See also *Planta* **37**: 676–696. 1950.]
- FLORIN, R. On the geological history of the Sciadopitineae. *Sv. Bot. Tidskr.* **16**: 260–270. 1922. [*Sciadopitys* and related leaf fossils; see also the recent treatment by MANUM.]
- . Untersuchungen zur Stammesgeschichte der Coniferales und Cordaitales. *Sv. Vet.-akad. Handl.* III. **10**: 1–588. pls. 1–58. 1931. [Classic treatment of vegetative anatomy of the conifers.]
- . Evolution in cordaites and conifers. *Acta Horti Berg.* **15**: 285–388. 1951. [Evolution of the coniferous ovulate cone.]
- . On *Metasequoia*, living and fossil. *Bot. Not.* **1952**: 1–29. 1952. [Review of morphology, history, and relationships; range map.]
- . The female reproductive organs of conifers and taxads. *Biol. Rev.* **29**: 367–389. 1954.
- . The systematics of the gymnosperms. Pp. 323–403 in E. L. KESSEL, ed., *A century of progress in the natural sciences, 1853–1953*. San Francisco. 1955. [Historical review, mostly of morphology.]
- . The distribution of conifer and taxad genera in time and space. *Acta Horti Berg.* **20**: 121–312. 1963. [Maps of current and fossil distribution for all genera of the Cupressaceae *s.l.*]
- & J. B. BOUTELJE. External morphology and epidermal structure of leaves in the genus *Libocedrus*, *s. lat.* *Acta Horti Berg.* **17**: 7–37. 1954.
- FLORY, W. S. Chromosome numbers and phylogeny in the gymnosperms. *Jour. Arnold Arb.* **17**: 83–89. 1936. [Notes the shared derived basic number,  $x = 11$ , of the Cupressaceae and the Taxodiaceae.]
- FOWELLS, H. A., compiler. Silvics of forest trees of the United States. U. S. Dep. Agr. Agr. Handb. **271**. 762 pp. 1965. [Includes *Calocedrus*, *Chamaecyparis*, *Juniperus*, *Sequoia*, *Sequoiadendron*, *Taxodium*, *Thuja*.]
- GADEK, P. A., & C. J. QUINN. Biflavones of the subfamily Callitroideae, Cupressaceae. *Phytochemistry* **22**: 969–972. 1983.
- & ———. Biflavones of the subfamily Cupressoideae, Cupressaceae. *Ibid.* **24**: 267–272. 1985.
- & ———. Biflavones and the affinities of *Cupressus funebris*. *Ibid.* **26**: 2551, 2552. 1987. [Biflavonyl profile does not support transfer to *Chamaecyparis*.]
- & ———. Pitting of transfusion tracheids in Cupressaceae. *Austral. Jour. Bot.* **36**: 81–92. 1988. [Unusual types are shared by certain genera of Cupressoideae and Callitroideae.]
- GAUSSEN, H. Les Taxodiacees. In: *Les gymnospermes: actuelles et fossiles*. *Trav. Lab. Forest. Toulouse*, Tome II, Vol. I, Chap. XII: 1–64. 1967. Les Cupressacées. *Ibid.* Chap. XIII: 1–326. 1968. [Worldwide treatment of the Taxodiaceae and Cupressaceae.] Bibliographie. *Ibid.* Tome II, Vol. I, Partie III: 1–180. 1979. [Bibliography for the entire work.]
- GEIGER, H., & C. QUINN. Biflavonoids. Pp. 692–742 in J. B. HARBORNE, T. J. MABRY,

- & H. MABRY, eds., *The flavonoids*. Vol. 2. London. 1975. [Cupressaceae, 720–722, 729–732.]
- & ———. *Biflavonoids*. Pp. 505–534 in J. B. HARBORNE & T. J. MABRY, eds., *The flavonoids: advances in research*. London and New York. 1982. [An updated summary.]
- GIVNISH, T. J. Ecological constraints on the evolution of breeding systems in seed plants: dioecy and dispersal in gymnosperms. *Evolution* **34**: 959–972. 1980. [Dioecy strongly correlated with seed dispersal by animals.]
- GORDON, G. *The pinetum*. xxiv + 484 pp. London. 1858.
- GREGUSS, P. *Identification of living gymnosperms on the basis of xylotomy*. 263 pp. 350 pls., 8 tables. Budapest. 1955.
- . *Xylotomy of the living conifers*. 172 + 329 pp. Budapest. 1972 [Cupressaceae, 19, 20, 86–109, pls. 8, 9, 84–114.]
- GULLINE, H. F. The cytology of *Athrotaxis*. *Pap. Proc. Royal Soc. Tasmania* **86**: 131–136. 1952. [All three species  $2n = 22$ .]
- HAIR, J. B. The chromosomes of the Cupressaceae. I. Tetraclineae and Actinostrobaeae (Callitroideae). *New Zealand Jour. Bot.* **6**: 277–284. 1968. [Counts for species of *Actinostrobus*, *Callitris*, and *Tetraclinis*, each  $2n = 22$ , and *Fitzroya cupressoides*,  $2n = 44$ .]
- HARDIN, J. W. Studies of the southeastern United States flora. II. The gymnosperms. *Jour. Elisha Mitchell Sci. Soc.* **87**: 43–50. 1971. [Cupressaceae *s.l.*, 48, 49; *Callitris* reported as naturalized in Florida.]
- HART, J. A. A cladistic analysis of conifers: preliminary results. *Jour. Arnold Arb.* **68**: 269–307. 1987. [Cladograms at both intergeneric and interfamilial levels; character states tabulated for the genera of the Cupressaceae *s.l.*]
- HAYATA, B. The Sciadopityaceae represented by *Sciadopitys verticillata* Sieb. et Zucc., an endemic species of Japan. (In Japanese and Latin.) *Bot. Mag. Tokyo* **45**: 567–569. 1931.
- . The Taxodiaceae should be divided into several distinct families, i.e., the Limnopytiaceae, Cryptomeriaceae, Taiwaniaceae, and the Cunninghamiaceae, and further *Tetraclinis* should represent a distinct family, the Tetraclinaceae. (In Japanese and Latin.) *Ibid.* **46**: 24–27. 1932.
- HEGNAUER, R. *Chemotaxonomie der Pflanzen*. Band 1. Thallophyten, Bryophyten, Pteridophyten und Gymnospermen. 517 pp. Basel and Stuttgart. 1962. [Cupressaceae, 342–372, 478–480; Taxodiaceae, 421–429, 481, 482.] Band 7. Nachträge zu Band 1 und Band 2. xii + 804 pp. Basel, Boston, and Stuttgart. 1986. [Cupressaceae, 491–504, 801; Taxodiaceae, 535–540; extensive literature review.]
- . Biochemistry, distribution and taxonomic relevance of higher plant alkaloids. *Jour. Nat. Prod.* **27**: 2423–2427. 1988. [Alkaloids reported for *Athrotaxis*.]
- HENRY, A., & M. MCINTYRE. The swamp cypresses, *Glyptostrobus* of China and *Taxodium* of America, with notes on allied genera. *Proc. Irish Acad. B.* **37**: 90–116. pls. 1–8. 1926.
- HICKEL, R. Graines et plantules des conifères. *Bull. Soc. Dendrol. France* **19**: 13–115; **20**: 134–204. 1911. [Cupressaceae, **19**: 30–48 (seeds), **20**: 141–159 (seedlings).]
- HIDA, M. The comparative study of Taxodiaceae from the standpoint of the development of the cone scale. (In Japanese; English summary.) *Bot. Mag. Tokyo* **70**: 44–51. 1957. [Taxodiaceae divided into five groups on the basis of pattern of cone-scale development.]
- . The systematic position of *Metasequoia*. (In Japanese; English summary.) *Ibid.* **75**: 316–323. 1962.
- HILL, T. G., & E. DE FRAINE. On the seedling structure of gymnosperms. I. *Ann. Bot.* **22**: 689–712. *pl.* 35. 1908. [Anatomy and morphology of several genera of Cupressaceae, including *Chamaecyparis*, *Juniperus*, and *Thuja*.]
- HIRMER, M. Die Blüten der Coniferen. I. Entwicklungsgeschichte und vergleichende



- Morphologie des weiblichen Blütenzapfens der Coniferen. *Bibliot. Bot.* **114**(1): 1–100. pls. A–K, 1–12. 1936. [Excellent illustrations of ovulate-cone morphology and development in Cupressaceae and Taxodiaceae.]
- HO, R. H., & O. SZIKLAI. Fine structure of pollen surface of some Taxodiaceae and Cupressaceae species. *Rev. Palaeobot. Palynol.* **15**: 17–26. 1973. [*Chamaecyparis*, *Cryptomeria*, *Cunninghamia*, *Sciadopitys*, *Sequoia*, *Taxodium*.]
- HU, H.-H., & W.-C. CHENG. On the new family Metasequoioaceae and on *Metasequoia glyptostroboides*, a living species of the genus *Metasequoia* found in Szechuan and Hupeh. *Bull. Fan Mem. Inst. Biol.* **1**: 153–161. 1948.
- HU, Y.-S., & B.-J. YAO. Transfusion tissue of gymnosperm leaves. *Bot. Jour. Linn. Soc.* **83**: 263–272. 1981.
- JANCHEN, E. Das System der Koniferen. Sitz.-ber. Akad. Wiss. Math.-Naturw. Wien I. **158**: 155–262. 1949 [1950].
- KAEISER, M. The pollen of certain Taxodiaceae. *Trans. Illinois Acad. Sci.* **32**: 94, 95. 1939. [*Cryptomeria*, *Cunninghamia*, *Sciadopitys*, *Sequoia*, *Sequoiadendron*, *Taxodium*.]
- KENT, A. H. Veitch's manual of the Coniferae. ed. 2. 564 pp. London. 1900.
- KERN, F. D. A revised taxonomic account of *Gymnosporangium*. ix + 134 pp. University Park, Pennsylvania. 1973. [Fungal parasites of *Calocedrus*, *Chamaecyparis*, *Cupressus*, *Juniperus*.]
- KHAN, A. G., & P. G. VALDER. Occurrence of root nodules in Ginkgoales, Taxales, and Coniferales. *Proc. Linn. Soc. New S. Wales* **97**: 35–41. 1972. [Nodules seen in *Sciadopitys* but not in the Cupressaceae *s.l.*]
- KHOSHOO, T. N. Polyploidy in gymnosperms. *Evolution* **13**: 24–39. 1959.
- . Chromosome numbers in gymnosperms. *Silvae Genet.* **10**: 1–9. 1961. [Comprehensive summary of the literature.]
- KONAR, R. N. Investigations on the development of the male cones in *Fitzroya cupressoides* (Mol.) Johnst. and *Pilgerodendron uviferum* (Dom.) Flor. *Phytomorphology* **12**: 190–195. 1962.
- & Y. P. OBEROL. Recent work on reproductive structures of living conifers and taxads—a review. *Bot. Rev.* **35**: 89–116. 1969.
- KRÜSSMANN, G. Handbuch der Nadelgehölze. ed. 2, revised by H.-D. WARD. [6 +] 396 pp. 160 pls. Berlin and Hamburg. 1983. [Also published in English as G. KRÜSSMANN, Manual of cultivated conifers. M. E. EPP, translator. 361 pp. 160 pls. Portland, Oregon. 1985.]
- KUO, S. R., T. T. WANG, & T. C. HUANG. Karyotype analysis of Formosan gymnosperms. *Taiwania* **17**: 66–80. 1972. [Karyotypes and chromosome counts for species of *Chamaecyparis*, *Cunninghamia*, and *Taiwania*; all  $2n = 22$ .]
- LAI, Y. Z. A proposed biogenetic pathway of tropolones in family Cupressaceae. *Celulose Chem. Tech.* **5**: 621–623. 1971.
- LAWSON, A. A. The gametophytes, archegonia, fertilization, and embryo of *Sequoia sempervirens*. *Ann. Bot.* **18**: 1–28. 1904.
- . The gametophytes and embryo of Cupressineae with special reference to *Libocedrus decurrens*. *Ibid.* **21**: 281–301. 1907. [*Calocedrus decurrens*.]
- LEBRETON, P. Les Cupressales: une définition chimiosystématique. *Candollea* **37**: 243–256. 1982. [Flavonoid constituents of Cupressaceae and Taxodiaceae.]
- LEMOINE-SÉBASTIAN, C. Vascularisation du complexe bractée-écaille dans le cône femelle des Cupressacées. *Bot. Rhodon. A.* **7**: 3–27. 1969.\* [See also *ibid.* **11**: 177–187. 1971.]
- . Étude comparative de la vascularisation et du complexe séminal chez les Cupressacées. *Phytomorphology* **22**: 246–260. 1972.
- LI, H.-L. A reclassification of *Libocedrus* and Cupressaceae. *Jour. Arnold Arb.* **34**: 17–36. 1953a. [Cupressaceae *s.s.* split into the largely Southern Hemisphere Callitroideae and the Northern Hemisphere Cupressoideae.]

- . Present distribution and habitats of the conifers and taxads. *Evolution* 7: 245–261. 1953b.
- LI, L.-C. Preliminary report on the karyotype of *Glyptostrobus pensilis*. *Helongjiang Linye Kexueyuan Linye Keji* 5: 5, 6. 1984.\* [ $2n = 22$ .]
- & P.-S. HU. Karyotype analyses in *Platycladus orientalis* and *Fokienia hodginsii*. (In Chinese; English summary.) *Acta Bot. Yunnan* 6: 447–451. [Both with  $2n = 22$ .]
- LITTLE, E. L., JR. Atlas of the United States trees. Vol. 1. Conifers and important hardwoods. U. S. Dep. Agr. Forest Serv. Misc. Publ. 1146. v + 9 pp. 2 base maps, 200 species maps, 9 overlay maps. 1971. [Detailed range maps for all North American species of the Cupressaceae *s.l.*]
- . Checklist of United States trees (native and naturalized). U. S. Dep. Agr. Agr. Handb. 531. iv + 375 pp. 1979.
- . The Audubon Society field guide to North American trees. Eastern region. 714 pp. New York. 1980. [Cupressaceae *s.l.*, 302–313, figs. 27, 28, 31–39.]
- LIU, T.-S., & H.-J. SU. Biosystematic studies on *Taiwania* and numerical evaluations of the systematics of Taxodiaceae. *Taiwan Mus. Spec. Publ.* 2: 1–113. 1983. [Genera of the Taxodiaceae compared in detail.]
- LONGMAN, K. A., J. DICK, & C. N. PAGE. Cone induction with gibberellin for taxonomic studies in Cupressaceae and Taxodiaceae. *Biol. Pl.* 24: 195–201. 1982.
- LOTOVA, L. I. Anatomical structure of the bark of Cupressaceae. (In Russian; English summary.) *Moscow Univ. Biol. Sci. Bull.* 36: 1–7. 1981.\*
- MAHESHWARI, P., & H. SINGH. The female gametophyte of gymnosperms. *Biol. Rev.* 42: 88–130. 1967.
- MANUM, S. B. Mesozoic *Sciadopitys*-like leaves with observations on four species from the Jurassic of Andoya, northern Norway and emendation of *Sciadopityoides* Sveshnikova. *Rev. Palaeobot. Palynol.* 51: 145–168. 1987. [Identity of early *Sciadopitys* fossils confirmed.]
- MARTINEZ, M. Las Pinaceas mexicanas. ed. 3. 400 pp. Mexico City. 1963. [Cupressaceae, *s.l.*, 161–400.]
- MASTERS, M. T. Notes on the genera of Taxaceae and Coniferae. *Bot. Jour. Linn. Soc.* 30: 1–41. 1893. [Cupressaceae, 11–25.]
- . On *Taxodium* and *Glyptostrobus*. *Jour. Bot. London* 38: 37–40. 1900.
- MAZZEO, P. M. Notes on the conifers of the Shenandoah National Park. *Castanea* 31: 240–247. 1966. [*Juniperus communis*, *J. virginiana*, *Thuja occidentalis*.]
- MEHRA, P. N., & T. N. KHOSHOO. Cytology of conifers. I. *Jour. Genet.* 54: 165–180. pl. 5. 1956. [Chromosome counts for species of *Actinostrobus*, *Callitris*, *Cryptomeria*, *Cunninghamia*, *Cupressus*, *Juniperus*, *Taxodium*, *Tetraclinis*, *Thuja*, and *Widdringtonia*, all  $2n = 22$ .]
- MILLAY, M. A., & T. N. TAYLOR. Evolutionary trends in fossil gymnosperm pollen. *Rev. Palaeobot. Palynol.* 21: 65–91. 1976. [Loss of saccae, as in the Cupressaceae, is the derived state in the conifers.]
- MILLER, C. N., JR. Mesozoic conifers. *Bot. Rev.* 43: 217–280. 1977. [Cupressaceae, 242–250; see also MILLER, 1988.]
- . Current status of Paleozoic and Mesozoic conifers. *Rev. Palaeobot. Palynol.* 37: 99–114. 1982. [Preliminary phylogenetic comparisons of fossil and extant genera based on ovulate cone characters.]
- . The origin of modern conifer families. Pp. 448–486 in C. B. BECK, ed., *Origin and evolution of gymnosperms*. New York. 1988. [Seed and ovulate-cone characters polarized by outgroup comparison; phylogenetic analysis supports merger of the Taxodiaceae and the Cupressaceae.]
- & D. R. CRABTREE. A new taxodiaceous seed cone from the Oligocene of Washington. *Am. Jour. Bot.* 76: 133–142. 1989. [*Cunninghamiostrobus Goedertii*; relationships of *Cunninghamia* to other taxodiaceous genera discussed.]
- MORLEY, T. On leaf arrangement in *Metasequoia glyptostroboides*. *Proc. Natl. Acad. Sci. U.S.A.* 34: 574–578. 1948.

- MOSELEY, M. F. Contributions to the life history, morphology, and phylogeny of *Widdringtonia cupressoides*. *Lloydia* 6: 109-132. 1943. [Discusses relationships in the Cupressaceae s.s.]
- NEGER, F. W. Die Nadelhölzer (Koniferen) und übrigen Gymnospermen. 185 pp. Leipzig. 1907.
- OLADELE, F. A. Inner surface patterns of cuticles in Cupressaceae. *Canad. Jour. Bot.* 61: 1222-1231. 1983a.
- . Scanning electron microscope study of stomatal-complex configuration in Cupressaceae. *Ibid.* 1232-1240. 1983b.
- OUDEN, P. DEN, & B. K. BOOM. Manual of cultivated conifers. x [+ 2] + 526 pp. The Hague. 1965.
- OWENS, J. N., & S. SIMPSON. Pollen from conifers native to British Columbia. *Canad. Jour. Forest Res.* 16: 955-967. 1986. [SEM and LM photographs and descriptions; includes *Chamaecyparis*, *Juniperus*, *Thuja*.]
- PARLATORE, P. Coniferae. In: A. DE CANDOLLE, *Prodr.* 16(2): 361-521. 1868. [Cupressaceae s.l., 432-493.]
- PATEL, R. N. Wood anatomy of Cupressaceae and Araucariaceae indigenous to New Zealand. *New Zealand Jour. Bot.* 6: 9-18. 1968. [*Libocedrus*.]
- PEIRCE, A. S. Anatomical interrelationships of the Taxodiaceae. *Trop. Woods* 46: 1-15. 1936.
- . Systematic anatomy of the woods of the Cupressaceae. *Ibid.* 49: 5-21. 1937.
- PENHALLOW, D. P. The generic characters of the North American Taxaceae and Coniferae. *Trans. Roy. Soc. Canada*, II, 2(4): 33-57. pls. 1-6. 1896. [Wood anatomy of *Calocedrus*, *Chamaecyparis*, *Cupressus*, *Juniperus*, *Sequoia*, *Sequoiadendron*, *Taxodium*, *Thuja*.]
- PHILLIPS, E. W. J. Identification of softwoods by their microscopic structure. *Dep. Sci. Industr. Res. (London) Forest Prod. Res. Bull.* 22. iii + 56 pp. 3 pls. 1948. [A similar account appeared in *Bot. Jour. Linn. Soc.* 52: 59-320. 1941.]
- PILGER, R. Taxodiaceae. In: A. ENGLER, *Nat. Pflanzenfam.* ed. 2. 13: 342-360. Cupressaceae. *Ibid.* 361-403. 1926. [Detailed illustrations of the genera, *figs.* 179-215.]
- & H. MELCHIOR. Gymnospermae. In: H. MELCHIOR, *A. Engler's Syllabus der Pflanzenfam.* ed. 12. 1: 312-344. 1954. [Cupressaceae s.l., 332-337.]
- PRICE, R. A., & J. M. LOWENSTEIN. An immunological comparison of the Sciadopityaceae, Taxodiaceae, and Cupressaceae. *Syst. Bot.* 14: 141-149. 1989. [Immunological data indicate that the Cupressaceae and Taxodiaceae form a single lineage, with the Cupressaceae s.s. a monophyletic subset, while *Sciadopitys* is a distant outgroup.]
- PROPACH-GEISELER, C. Die Blüten der Coniferen II. Zur Morphologie und Entwicklungsgeschichte der weiblichen Blütenzapfen der Cupressaceen. *Bibliot. Bot.* 114(2): 1-56. pls. 1-13. 1936.
- QUINN, C. J., & P. A. GADEK. Sequence of xylem differentiation in leaves of Cupressaceae. *Am. Jour. Bot.* 75: 1344-1351. 1988. [Species of *Callitris*, *Chamaecyparis*, *Cupressus*, *Juniperus*, and *Widdringtonia* compared.]
- RADAIS, M. Contribution à l'étude de l'anatomie comparée du fruit des conifères. *Ann. Sci. Nat. Bot.* VII. 19: 165-368. 1894.
- RADFORD, A. E., H. E. AHLES, & C. R. BELL. Manual of the vascular flora of the Carolinas. lxi + 1183 pp. Chapel Hill. 1968. [Taxodiaceae, Cupressaceae s.l., 40-43.]
- REHDER, A. Manual of cultivated trees and shrubs hardy in North America, exclusive of the subtropical and warmer temperate regions. ed. 2. xxx + 996 pp. New York. 1940. [Cupressaceae s.l., 42-68.]
- . Bibliography of cultivated trees and shrubs hardy in the cooler temperate regions of the Northern Hemisphere. xl + 825 pp. Jamaica Plain, Massachusetts. 1949. [Detailed nomenclatural treatment; Cupressaceae s.l., 41-64.]
- ROTH, I. Histogenese und morphologische Deutung der Doppelnadeln von *Sciadopitys*. *Flora* 152: 1-23. 1962.
- ROUANE, P. Étude comparée de la répartition des ramifications au cours de l'ontogenèse

- de quelques Cupressacées. Trav. Lab. Forest. Toulouse, Tome I, Vol. IX, Art. III: 1-277. 1973.
- RUSHFORTH, K. D. Conifers. 232 pp. London. 1987.
- SARGENT, C. S. *Silva N. Am.* **10**, vii + 159 pp. pls. 497-537. 1896. [Cupressaceae *s.l.*, 69-154, pls. 516-537.] *Ibid.* **14**, 152 pp. pls. 705-740. 1902. [Cupressaceae *s.l.*, 89-96, pls. 738-740.]
- . *Manual of the trees of North America (exclusive of Mexico)*, ed. 2, xxvi + 910 pp. Boston and New York. 1926. [Cupressaceae *s.l.*, 61-90.]
- SAX, K., & H. J. SAX. Chromosome number and morphology in the conifers. *Jour. Arnold Arb.* **14**: 356-374. pls. 75, 76. 1933. [Chromosome numbers for species of *Chamaecyparis*, *Cryptomeria*, *Juniperus*, *Platycladus*, *Taiwania*, *Taxodium*, and *Thuja*, all  $2n = 22$  except for a tetraploid count in *J. chinensis*; karyotypes for all but the first two genera.]
- SAXTON, W. T. Contributions to the life history of *Tetraclinis articulata* Masters with some notes on the phylogeny of the Cupressoideae and Callitroideae. *Ann. Bot.* **27**: 577-605. 1913a.
- . The classification of conifers. *New Phytol.* **12**: 242-262. 1913b. [Cupressaceae and Taxodiaceae combined on the basis of reproductive characters.]
- SAYLOR, L. C., & H. A. SIMONS. Karyology of *Sequoia sempervirens*: karyotype and accessory chromosomes. *Cytologia* **35**: 294-303. 1970.
- SCHLARBAUM, S. E., L. C. JOHNSTON, & T. TSUCHIYA. Chromosome studies of *Metasequoia glyptostroboides* and *Taxodium distichum*. *Bot. Gaz.* **144**: 559-565. 1983.
- & T. TSUCHIYA. Cytotaxonomy and phylogeny in certain species of Taxodiaceae. *Pl. Syst. Evol.* **147**: 29-54. 1984. [Karyotypes of *Cryptomeria*, *Cunninghamia*, *Metasequoia*, *Sciadopitys*, *Sequoia*, *Sequoiadendron*, *Taiwania*, and *Taxodium* compared.]
- & ———. Karyological derivation of *Sciadopitys verticillata* Sieb. et Zucc. from a pro-taxodiaceous ancestor. *Bot. Gaz.* **146**: 264-267. 1985.
- SILBA, J. An international census of the Coniferae. 1. *Phytologia Mem.* **7**: 1-79. 1984. [Worldwide conspectus of the species of conifers, with several new varietal combinations for the Cupressaceae.]
- SINGH, H. Embryology of gymnosperms. In: K. LINSBAUER, *Handbuch der Pflanzen-anatomic*, ed. 2, Band 10, Teil 2, xii + 302 pp. Berlin. 1978. [Male and female gametophytes; pollination mechanisms; embryogeny; extensive bibliography.]
- & J. CHATTERJEE. A contribution to the life history of *Cryptomeria japonica* D. Don. *Phytomorphology* **13**: 429-445. 1963. [Thorough review of cone morphology and embryology.]
- & Y. P. OBEROI. A contribution to the life history of *Biota orientalis* Endl. *Phytomorphology* **12**: 373-393. 1962. [*Platycladus orientalis*.]
- SMALL, J. K. *Manual of the southeastern flora*. xxii + 1554 pp. New York. 1933. [Cupressaceae *s.l.*, 8-11; Cupressaceae and Taxodiaceae merged under Juniperaceae.]
- SPORNE, K. R. *The morphology of gymnosperms*, ed. 2. 216 pp. London. 1974.
- STAFFORD, H. A., & H. H. LESTER. Proanthocyanidins in needles from six genera of the Taxodiaceae. *Am. Jour. Bot.* **73**: 1155-1162. 1986. [*Cryptomeria*, *Metasequoia*, *Sciadopitys*, *Sequoia*, *Sequoiadendron*, *Taxodium*.]
- STEBBINS, G. L., JR. The chromosomes and relationships of *Metasequoia* and *Sequoia*. *Science* **108**: 95-98. 1948.
- STERLING, C. Some features in the morphology of *Metasequoia*. *Am. Jour. Bot.* **36**: 461-471. 1949. [Thorough study of morphology and anatomy of *M. glyptostroboides*.]
- . Structure of the male gametophyte in gymnosperms. *Biol. Rev.* **38**: 167-203. 1963.
- STRASBURGER, E. *Die Coniferen und die Gnetaceen*. 442 pp. Jena. 1872. [Important early accounts of development and morphology.]
- SUROVA, T. D., & V. KVAVADZE. Sporoderm ultrastructure in some gymnosperms (*Meta-*

- sequoia*, *Cunninghamia*, *Sciadopitys*). (In Russian; English summary.) Bot. Zhur. **73**: 34-44. 1988. [LM, SEM, TEM comparisons; *Sciadopitys* is quite dissimilar to the other genera.]
- SUSZKA, B. The seedlings and so-called juvenile forms of the Cupressaceae family. (In Polish; English summary.) Polsk. Towarz. Bot. Dendrol. Roczn. **11**: 71-131. 1956.
- SUZUKI, M. The course of resin canals in the shoots of conifers. II. Araucariaceae, Cupressaceae and Taxodiaceae. Bot. Mag. Tokyo **92**: 253-274. 1979a. [See also *ibid.* **92**: 333-353. 1979b.]
- TAHARA, M. Contributions to the morphology of *Sciadopitys verticillata*. Cytologia, Fujii Jubilee Vol. **1**: 14-19. 1937.
- . The gametophytes, fertilization and proembryo of *Sciadopitys verticillata*. Sci. Rep. Tôhoku Univ. Biol. **15**: 19-28. 1940.
- TAKASO, T., & P. B. TOMLINSON. Aspects of cone and ovule ontogeny in *Cryptomeria* (Taxodiaceae). Am. Jour. Bot. **76**: 692-705. 1989. [SEM and LM studies of cone-scale development.]
- TAKEUCHI, M. Studies on the germination of the pollen grains in conifers. I. Jap. Jour. Bot. **14**: 13-21. 1953.
- TERASAKA, O. Nuclear differentiation of male gametophytes in gymnosperms. Cytologia **47**: 27-46. 1982. [Pattern of cell division in microgametophytes of *Cryptomeria*, *Metasequoia*, *Sequoia*, and *Juniperus conferta*.]
- TIEGHEM, P. VAN. Anatomie comparée de la fleur femelle et du fruit des Cycadées, des Conifères et des Gnetaées. Ann. Sci. Nat. Bot. V. **10**: 269-304. 1869.
- UENO, J. Morphology of pollen of *Metasequoia*, *Sciadopitys*, and *Taiwania*. Jour. Inst. Polytech. Osaka City Univ. D. **2**: 22-26. 1951.
- . Some palynological observations of Taxaceae, Cupressaceae, and Araucariaceae. *Ibid.* **10**: 75-87. 1959. [LM and TEM comparisons of pollen structure.]
- . Studies on pollen grains of Gymnospermae: concluding remarks to the relationships between Coniferae. *Ibid.* **11**: 109-136. *pl. 1, table 1*. 1960a.
- . On the fine structure of the cell walls of some gymnosperm pollen. Biol. Jour. Nara Women's Univ. **10**: 19-25. 1960b.
- VIERRHAPPER, F. Entwurf eines neuen Systemes der Coniferen. Abh. Zool.-Bot. Ges. Wien **5**(4): 1-56. 1910.
- VON RUDLOFF, E. Volatile leaf oil analysis in chemosystematic studies of North American conifers. Biochem. Syst. Ecol. **2**: 131-167. 1975. [Terpene composition of several species of *Chamaecyparis*, *Juniperus*, and *Thuja* compared.]
- WANG, F.-H., S.-C. LEE, & Z.-K. CHEN. The embryogeny of *Taiwania* in comparison with that of other genera of Taxodiaceae. (In Chinese; English summary.) Acta Phytotax. Sinica **18**: 129-137. *pl. 1*. 1979.
- WILSON, E. H. The conifers and taxads of Japan. Publ. Arnold Arb. **8**, xi + 91 pp. 59 *pls.* 1916.
- WODEHOUSE, R. P. Pollen grains. xv + 574 pp. New York. 1935. [Cupressaceae, *s.l.*, 247-250, 268-273.]
- WÓYCICKI, S. On the origin of the *Retinospora* forms in *Thuja*, *Biota*, and *Chamaecyparis*. Acta Soc. Bot. Polon. **23**: 443-458. 1954. [Reproductive plants retaining the juvenile leaf form (*Retinospora* types) apparently result from genetic mutations; plants propagated vegetatively from seedlings revert to adult leaf form.]
- YAMAZAKI, T., & M. TATEOKA. On the identifications of the pollen of Taxodiaceae. (In Japanese.) Saikyo Univ. Fac. Agr. Sci. Rep. **8**: 10-16. 1956.\*
- YATAGAI, M., & T. SATO. Terpenes of leaf oils from conifers. Biochem. Syst. Ecol. **14**: 469-478. 1986. [*Cryptomeria*, *Sciadopitys*.]
- , & T. TAKAHASHI. Terpenes of leaf oils from Cupressaceae. Biochem. Syst. Ecol. **13**: 377-385. 1985. [Profiles from species of *Chamaecyparis*, *Juniperus*, *Thuja*, *Thujopsis*.]
- ZAVARIN, E., L. LAWRENCE, & M. C. THOMAS. Compositional variations of leaf mono-

terpenes in *Cupressus macrocarpa*, *C. pygmaea*, *C. Goveniana*, *C. Abramsiana*, and *C. Sargentii*. *Phytochemistry* **10**: 379-393. 1971.

———, L. V. SMITH, & J. G. BICHO. Tropolones of Cupressaceae—III. *Phytochemistry* **6**: 1387-1394. 1967. [Chemosystematic investigation of *Cupressus*.]

KEY TO THE GENERA OF CUPRESSACEAE (INCLUDING TAXODIACEAE)  
IN THE SOUTHEASTERN UNITED STATES

General characters: *Monoecious (or dioecious) evergreen or winter-deciduous trees or shrubs; foliage leaves alternate (often appearing 2-ranked) and linear to linear-lanceolate, or opposite to whorled and needlelike, awl-shaped, or scale-like; pollen cones with spirally arranged, opposite, or whorled microsporophylls, each sporophyll with 2 to 10 globose abaxial microsporangia; pollen nonsaccate, lacking prothallial cells; ovulate cones subglobose to ovoid or oblong; bracts and ovuliferous scales strongly fused in mature cones; scales peltate to ovate or oblong, alternate or opposite or whorled, bearing 1 to 6 [to 20] erect [or inverted] adaxial ovules; archegonia clustered; seeds with 2 (or 3) lateral wings [or 1 nearly terminal one] or wingless; cotyledons 2 to 6 (to 9); chromosome base number  $x = 11$ .*

- A. Foliage leaves alternate, linear to linear-subulate; branchlets winter deciduous. . . . 1. *Taxodium*.
- A. Foliage leaves opposite or whorled, mostly reduced and scalelike; branchlets evergreen.
- B. Branchlets forming flattened sprays.
- C. Cones globose; cone scales peltate. . . . 2. *Chamaecyparis*.
- C. Cones ovoid or ellipsoid; cone scales not peltate.
- D. Branchlets flattened in horizontal plane; seeds laterally winged; immature cone scales only slightly fleshy. . . . 3. *Thuja*.
- D. Branchlets flattened in vertical plane; seeds wingless; immature cone scales very fleshy. . . . *Platycladus*.<sup>6</sup>
- B. Branchlets not forming flattened sprays.
- E. Cone scales less than 1 cm long, fleshy, fused into indehiscent, berrylike structures. . . . 4. *Juniperus*.
- E. Cone scales more than 1 cm long, woody at maturity, with evident borders, separating to release seeds. . . . 5. *Callitris*.

1. *Taxodium* Richard, Ann. Mus. Hist. Nat. Paris **16**: 298. 1810.

Winter-deciduous [to evergreen] trees, pyramidal to narrowly conical when young, the crown often broad in older individuals; trunk much enlarged at base, often buttressed. Bark light- to reddish-brown, fibrous, ridged, often peeling in strips. Roots horizontal, often with cone-shaped "knees" projecting from water. Branches erect or spreading; branchlets dimorphic, those near the apex of the shoot persistent and with prominent axillary buds, those lower on the shoot without evident axillary buds and deciduous; winter buds globose, scaly. Juvenile leaves linear-lanceolate, whorled or spirally arranged; adult

<sup>6</sup>*Platycladus orientalis* (L.) Franco, native to eastern Asia, is commonly planted in our region and may occasionally escape (Little, 1979; Small) but needs further documentation before being considered naturalized (Wunderlin, pers. comm.).

leaves spirally arranged, either 2-ranked by twisting of leaf bases, thin and linear-lanceolate, or 5- to 8-ranked, linear-subulate and keeled, closely appressed to the branches (the 2 leaf forms on the same or different trees). Pollen cones small, ovoid, in long, drooping racemes or panicles terminating the previous year's shoots; microsporophylls 6 to 10 [to 15], broadly ovate to peltate; microsporangia (2 to) 4 to 9 (or 10), globose, pendulous, in 2 rows at base of the abaxial side of the microsporophyll; pollen with evident papilla. Ovulate cones terminal on short, scaly branchlets near ends of previous year's branchlets, maturing in 1 year; immature bract-scale complexes spirally imbricate, each with (1 or) 2 (or 3) erect, bottle-shaped ovules; mature ovulate cones subglobose to somewhat ovoid; cone scales thick, woody, peltate, 4-sided, with mucronulate umbo; resin vesicles with blood-red resin prominent on interior portions of cone scale. Seeds usually 2 on the adaxial side of each cone scale, erect, attached laterally to the stalk of the scale by a large, pale hilum; seed coat thick, woody, lustrous, with 3 small, unequal corky wings; cotyledons 3 to 9. Chromosome number  $2n = 22$ . TYPE SPECIES: *Taxodium distichum* (L.) Rich. (Name from Greek, in allusion to the yewlike leaves of the type species.)—BALD CYPRESS, SWAMP CYPRESS.

A genus of two closely related species or perhaps a single polymorphic one, native to swampy and riverine areas of the southeastern and central United States and from extreme southern Texas south through much of Mexico to Guatemala. The genus was widespread in Europe and western North America in the Tertiary, becoming extinct in these areas with climatic deterioration in the Pliocene (Florin, 1963).

There has been considerable disagreement concerning the number of species to recognize within *Taxodium*. Britton (1926), Dallimore & Jackson, and Rehder (1940) each recognized three species (*T. distichum* Rich. (bald cypress), *T. ascendens* Brongn. (pond cypress), and *T. mucronatum* Ten. (Tule tree, Montezuma cypress), although substantial intergradation has been reported, particularly between pond and bald cypresses.

Watson (1983, 1985), after reviewing morphological, anatomical, biochemical, and cytological data, concluded that the differences between the pond and bald cypresses are minor, showing considerable overlap and being subject to environmental modification. Watson thus suggested varietal status (as var. *imbricarium* (Nutt.) Croom) for the pond cypress, and this treatment is adopted here.

Montezuma cypress is somewhat more distinct in morphology and ecology and is allopatric in distribution (reaching extreme southern Texas from Mexico and Guatemala) and is thus usually treated as the separate species *Taxodium mucronatum*, although it may be more appropriately treated as a third variety, *T. distichum* var. *mexicanum* (Carr.) Gordon. It differs in being semievergreen, retaining its annual leafy shoots until after the new shoots have leafed out in winter or spring, and being considerably less cold hardy in cultivation than the other taxa. It has sometimes been reported to have larger, more glaucous ovulate cones (Henry & McIntyre) and longer pollen-cone-bearing branches, but more thorough sampling indicates considerable overlap for these features

(Brown, 1984; Little, 1980; Martínez, 1963). The smaller branches tend to be more drooping in the Montezuma cypress, and knees are only occasionally present (Martínez, 1950, 1963). Kaieser (1953) reported that the horizontal walls of the ray parenchyma cells are thinner in the Mexican taxon, while there is little difference in the wood anatomy of the bald and pond cypresses. Isozyme electrophoresis of population samples would be very useful in assessing the degree of genetic differentiation of Montezuma cypress from the other taxa.

*Taxodium distichum* var. *distichum*, bald cypress, swamp cypress,  $2n = 22$ , is a large tree (to 50 m) with the trunk angular at the base and the leaves two-ranked on the annual branchlets. The bark is usually thin and smooth, and the knees are usually slender. *Taxodium distichum* var. *distichum* is native on the Coastal Plain from southern Delaware to Florida, west to the valley of the Devil River in Texas, and northward in the Mississippi Embayment through Louisiana and Arkansas to southeastern Missouri and Tennessee, western and northwestern Kentucky, southern Illinois, and southwestern Indiana. The species occurs in riverine swamps that are usually inundated for several months of the year and in low, saturated stream-bank habitats and wet depressions in pine barrens. It attains its largest size in the Gulf and south Atlantic coastal areas, where it tends to form pure stands in the great river swamps. The species commonly occurs with water tupelo or tupelo (*Nyssa aquatica* L., *N. sylvatica* Marsh.) and also grows in drier habitats with red maple, water ash, and sweet gum.

*Taxodium distichum* var. *imbricarium* (Nutt.) Croom (*T. ascendens* Brongn., *T. imbricarium* (Nutt.) Harper, *T. distichum* var. *nutans* auct., non (Aiton) Sweet), pond cypress,  $2n = 22$ , is a smaller tree (to ca. 25 m in height) that occurs on the Atlantic and Gulf Coastal plains from southeastern Virginia to southeastern Louisiana. Its trunk has rounded ridges, and its appressed, subulate leaves are ca. 5–12 mm long on both annual and perennial branchlets. The bark tends to be thicker and more strongly furrowed than in var. *distichum*, and the knees, if present, are short and rounded.

Watson (1983) summarized the ecological differences between the bald and pond cypresses. Pond cypress tends to grow in pine-barren ponds, often underlain by limestone, whereas bald cypress generally occurs in riverine swamps. Additionally, the habitat of the pond cypress has a decreased water flow and is more prone to drought and fire; the pH is lower, and nutrients are less available. Neufeld and Watson (1983) have suggested that the pond cypress is a recent derivative of the bald cypress that evolved in response to harshening environments along the Coastal Plain, with the smaller, closely appressed leaves helping to reduce water loss.

*Taxodium* has often been considered to be closely related to the East Asian genus *Glyptostrobus*, which is similar in its habitat, possession of knees, pattern of cone-scale development, relatively large number of cotyledons (averaging ca. 5 or 6), and winter-deciduous branchlets (Britton, 1926; Henry & McIntyre; Hida, 1957; Pilger & Melchior). *Metasequoia* is also similar to *Taxodium* in being winter deciduous and having the pollen cones in a racemose arrangement, and it groups with *Taxodium* and *Glyptostrobus* in Hart's preliminary cladistic analyses. In contrast, immunological comparisons of seed proteins by Price &



Lowenstein indicate that *Taxodium* is most similar to *Glyptostrobus* and *Cryptomeria* and that *Metasequoia* is most similar to *Sequoia* and *Sequoiadendron*.

*Taxodium* is a very distinct genus, differing from the other winter-deciduous members of the family in a number of vegetative and reproductive characters. The knees of *Glyptostrobus* are curved and bent rather than conical and erect as in *Taxodium* (Henry & McIntyre). The older perennial branchlets of *Glyptostrobus* bear scalelike leaves that remain green for several years and have rows of white stomatal dots on the surface, whereas those of *Taxodium* bear elongate linear-subulate leaves that become brown and corky in the second year. The cones of *Glyptostrobus* are pyriform and terminal on the branchlet, have scales that are elongate and imbricate at maturity and lack prominent resin pockets, and have the bract and cone-scale united at the base but free at the tip. The body of the seed is small and ovoid, bearing a single long, nearly terminal wing. In contrast, the mature cones of *Taxodium* are globose to ellipsoid, are borne laterally on the major branchlets, and have peltate scales with the edges meeting but not overlapping. The seed body is larger, much thicker walled, and three-angled, with only small, corky wings in the angles. *Metasequoia* differs from *Taxodium* in a number of features, notably in its smaller, more flattened cone scales, its opposite rather than spirally arranged leaves and cone scales, and its strongly compressed seeds that are more than two (usually five to eight) per scale, each with two lateral wings and only two cotyledons (Florin, 1952; Stebbins).

*Taxodium* develops three unusual structures in response to flooding: buttswells, buttresses, and knees. The term "buttswell" refers to the enlarged basal portion of the trunk, while buttresses are longitudinal ridges on the buttswell. Variation in size and shape of these structures is associated with fluctuations in exposure of the areas to air or water during the early part of the growing season, with the height of the buttresses tending to correspond to the average depth of flooding. According to Kurz & Demaree, buttress development results from the simultaneous presence of water and air, while individuals grown under permanently flooded conditions or in well-drained soils not subject to flooding fail to develop buttswells or buttresses.

The well-known "cypress knees" are usually emergent, cone-shaped structures produced as extensions of the roots and may be as tall as 3-4 m (Brown, 1984). They may arise as small swellings on the upper surfaces of shallow adventitious roots (Shaler; Whitford) or may be formed from shallow roots growing upward and then bending sharply downward, with the geniculate point becoming the "knee" (Brown & Montz). Various functions have been attributed to the knees. One suggestion has been that they act as pneumatophores ("breathing organs") that funnel oxygen into the root system (Dickeson & Brown; Mattoon; Shaler). More recent experiments have shown, however, that little if any gas exchange occurs (Kramer *et al.*), and that no stomata, lenticels, or conducting tissues are found on the surface of the knees (Brown, 1984). Other possible functions include the storage of starch, which accumulates there in significant amounts (Brown & Montz), and stabilization of the plant during severe storms (Lamborn, 1890a). Removal of the knees appears to have little adverse affect on the trees, at least over the short term (Mattoon).

Despite considerable variation in the extent of buttressing, buttswells, and knees, some authors have attempted to use these features to distinguish bald cypress from pond cypress. Watson (1983) pointed out that their magnitude appears to be ecophenically determined since they generally do not develop if the stem is not exposed to flooding; they are thus of limited taxonomic utility.

Many bald-cypress trees reach considerable size and age. One in Louisiana measured ca. 13 m in circumference and 26.7 m in height (Brown & Montz). Some individuals of Montezuma cypress also attain great size and have multiple stems at the base. At Santa Maria de Tule in Oaxaca, the famous "Tule tree" is reported to have the largest diameter of any tree (ca. 12 m), although it appears to represent three individuals that have grown together (Cronemiller; Little, 1980). This tree has been estimated to be anywhere from 1000 to 3000 years old (Krüssmann).

The wood of *Taxodium* is known for its durability in contact with soil and severe weather. The heartwood is so durable that it has been called "the wood eternal" and has been used in several types of heavy construction. The Seminole Indians in Florida have also used the wood in construction and for fenceposts, stockades, and dugout canoes. More recently, it has been valued for interior woodwork, cooperage, fence posts, and railroad ties (Little, 1980). The wood of pond cypress is purportedly heavier and stronger than that of var. *distichum* (Harper, 1902). Wood production from *T. distichum* peaked at more than one billion board feet in 1913 but has subsequently declined substantially because of heavy cutting (Mattoon; Sternitzke). In recent years second-growth bald cypress has again built up in abundance in the southeastern United States.

The resin of *Taxodium mexicanum* has been used in Mexico as a cure for wounds, ulcers, and toothaches (Henry & McIntyre).

*Taxodium* is of some horticultural importance in the eastern United States and Europe and is frequently planted along watercourses and farms as a wind-break in China. Cultivars of *Taxodium* are hardy as far north as Massachusetts, New York, and Michigan and grow best in deep, sandy loam with plentiful moisture and good drainage (Fowells).

#### REFERENCES:

- Under family references see ALVIN & BOULTER; L. H. BAILEY; BEAN; BRITTON, 1908, 1926; CHANEY, 1951; COKER & TOTTEN; DALLIMORE & JACKSON; G. ERDTMAN; H. ERDTMAN & NORIN; FLORIN, 1931, 1952, 1963; FOWELLS; GAUSSEN, 1967; HARDIN; HART; HEGNAUER, 1962, 1986; HENRY & MCINTYRE; HIDA, 1957; KHOSHOO, 1961; KRÜSSMANN; LITTLE, 1971, 1979, 1980; LIU & SU; MARTÍNEZ, 1963; MEHRA & KHOSHOO; MILLER, 1977; PEIRCE, 1936; PHILLIPS; PILGER; PILGER & MELCHIOR; PRICE & LOWENSTEIN; REHDER, 1940, 1949; SARGENT, 1896, 1926; SAX & SAX; SCHLARBAUM, JOHNSON & TSUCHIYA; SMALL; STEBBINS; UENO, 1960B; AND WODEHOUSE.
- BEAVEN, G. F., & H. J. OOSTING. Pocomoke Swamp: a study of a cypress swamp on the eastern shore of Maryland. *Bull. Torrey Bot. Club* **66**: 367-389, 1939.
- BERNARD, J. M. The status of *Taxodium distichum* (L.) Richard (bald cypress) in New Jersey. *Bull. Torrey Bot. Club* **92**: 305-307, 1965. [Extant stands not native.]
- BLANCK, C. E. An ecological study of baldcypress (*Taxodium distichum* (L.) Richard)

- in eastern North Carolina. 180 pp. Unpubl. Master's thesis, East Carolina University, Greenville, North Carolina. 1980.\*
- BOWERS, L. J. Tree ring characteristics of baldcypress growing in varying flooding regimes in Barataria Basin, Louisiana. 175 pp. Unpubl. Ph.D. dissertation, Louisiana State University, Baton Rouge, Louisiana. 1981.\*
- BRONGNIART, A. Note sur quelques conifères de la tribu des Cupressinées. *Ann. Sci. Nat. Bot.* I. **30**: 176-191. 1833. [Pond and bald cypresses distinguished.]
- BROWN, C. A. Cypress—the tree unique: the wood eternal. *Jour. New York Bot. Gard.* **1**: 36-39. 1951.
- . Morphology and biology of cypress trees. Pp. 16-24 in K. C. EWEL & H. T. ODUM, eds., *Cypress swamps*. 1984. [*T. distichum*.]
- & G. N. MONTZ. Baldcypress, the tree unique, the wood eternal. xvi + 139 pp. *frontisp., 179 black & white, 9 color photographs*. Baton Rouge, Louisiana. 1986. [Reviewed by W. D. REESE, *Castanea* **52**: 128. 1987.]
- CAIN, S. A. Bald cypress, *Taxodium distichum* (L.) Rich., at Hovey Lake, Posey County, Indiana. *Am. Midl. Nat.* **16**: 72-82. 1934.
- CLEVENGER, S. V. The causes of cypress knees. *Am. Nat.* **24**: 581. 1890.
- COKER, W. C. On the gametophytes and embryo of *Taxodium*. *Bot. Gaz.* **36**: 1-27, 114-140. *pls. 1-11*. 1903. [*T. distichum*.]
- . The bald cypress. *Jour. Elisha Mitchell Sci. Soc.* **46**: 86-88. *pl. 7*. 1930. [An extremely large tree from Seminole County, Florida, illustrated.]
- COULTER, S. Histology of the leaf of *Taxodium*. I and II. *Bot. Gaz.* **14**: 76-81, 101-107. *pl. 11*. 1889.
- CRONMILLER, F. P. El sabino, the national tree of Mexico. *Jour. Forestry* **55**: 461, 462. 1957. [*T. mucronatum*.]
- CROSS, G. L. A note on the morphology of the deciduous shoot of *Taxodium distichum*. *Bull. Torrey Bot. Club* **66**: 167-172. 1939a.
- . The structure and development of the apical meristem in the shoots of *Taxodium distichum*. *Ibid.* 431-452. 1939b.
- . Development of the foliage leaves of *Taxodium distichum*. *Am. Jour. Bot.* **27**: 471-482. 1940.
- DEMAREE, D. Submerging experiments with *Taxodium*. *Ecology* **13**: 258-262. 1932. [Seeds and seedlings of *T. distichum* do not survive extended submergence.]
- DENUYL, D. Some observations on bald cypress in Indiana. *Ecology* **42**: 841-843. 1961.
- EWEL, K. C., & H. T. ODUM, eds. *Cypress swamps*. xviii + 472 pp. Gainesville, Florida. 1984. [Ecology of *T. distichum* swamps.]
- FAULKNER, S. P. Genetic variation of cones, seed, and nursery grown seedlings of baldcypress (*Taxodium distichum* (L.) Rich.) provenances. Unpubl. Master's thesis, Louisiana State University, Baton Rouge. 1982.\*
- GEIGER, H., & W. DE GROOT-PFLEIDERER. Die Biflavone von *Taxodium distichum*. *Phytochemistry* **12**: 465, 466. 1973.
- GOURLAY, W. B. The Mexican swamp cypress (*Taxodium mucronatum* Tenore). *Quart. Jour. Forestry* **34**: 53-61. 1940.
- HALL, G. W., G. M. DIGGS, JR., D. E. SOLTIS, & P. SOLTIS. Genetic uniformity of El Arbol del Tule (The Tule Tree). *Madroño* **37**: 1-5. 1990. [Electrophoretic analysis of enzymes of leaf material from each of 8 major segments and of 2 nearby trees. "The results are consistent with the hypothesis that the Tule Tree is one genetic individual."]
- HARPER, R. M. *Taxodium distichum* and related species, with notes on some geological factors influencing their distribution. *Bull. Torrey Bot. Club* **29**: 383-399. 1902.
- . Further observations on *Taxodium*. *Ibid.* **32**: 105-115. 1905.
- HARSHBERGER, J. W. The Mexican cypress. *Forest Leaves* **11**: 24. 1907.
- KAIESER, M. Morphology and embryogeny of the bald cypress, *Taxodium distichum* (L.) Rich. Unpubl. Ph.D. dissertation, University of Illinois, Champaign-Urbana. 1940.\*

- . Embryo development of the pond cypress (*Taxodium ascendens* Brongn.). Trans. Illinois Acad. Sci. **42**: 63–67. 1949.
- . Microstructure of the wood of the three species of *Taxodium*. Bull. Torrey Bot. Club **80**: 415–418. 1953. [Bald and pond cypresses not separable on the basis of wood anatomy, while Montezuma cypress has thinner horizontal walls on its ray-parenchyma cells.]
- KRAMER, P. J., W. S. RILEY, & T. T. BANNISTER. Gas exchange of cypress knees. Ecology **33**: 117–121. 1952. [Little evidence for gas exchange between roots and knees.]
- KURZ, H., & D. DEMAREE. Cypress buttresses and knees in relation to water and air. Ecology **15**: 36–41. 1934.
- & K. A. WAGNER. The role of adventitious roots in survival of cypress. (Abstract.) Jour. Tennessee Acad. Sci. **27**: 201. 1952.
- & ———. Factors in cypress dome development. Ecology **34**: 157–164. 1953. [Cypress domes are formed in depressions by the confluent tops of crowded *T. distichum* trees, with the shorter trees at the outer and drier edges apparently pruned by fire.]
- LAMBORN, R. H. The knees of the bald cypress: a new theory of their function. Garden Forest **3**: 21, 22. 1890a. [Knees help to anchor the tree against toppling in storms.]
- . The knees of *Taxodium distichum*. Am. Nat. **24**: 333–340. pl. 12. 1890b.
- LANGDON, O. G. Silvical characteristics of baldcypress. U. S. Dep. Agr. Forest Serv. Southeast. Exper. Sta. Pap. **94**, 7 pp. 1 fig. 1958.
- MARTÍNEZ, M. El ahuehuete (*Taxodium mucronatum* Ten.). Anal. Inst. Biol. México **21**: 25–82. 1950.
- MONTZ, G. N., & A. CHERUBINI. An ecological study of a baldcypress swamp in St. Charles Parish, Louisiana. Castanea **38**: 378–386. 1973.
- NEUFELD, H. S. Ecophysiological implications of tree architecture for two cypress taxa. *Taxodium distichum* (L.) Rich. and *T. ascendens* Brongn. Bull. Torrey Bot. Club **113**: 118–124. 1986.
- RAO, A. R., & J. P. TEWARI. On the foliar sclereids of *Taxodium distichum* Rich. Proc. Natl. Inst. Sci. India **27**: 41–45. 1961.\*
- SHALER, N. S. Notes on *Taxodium distichum*, or bald cypress. Mem. Mus. Zool. Harvard Univ. **16**: 1–15. 1887.\*
- SHARMA, G. K., & L. MADSEN. Variation in bald cypress from different habitats. Jour. Tennessee Acad. Sci. **53**: 115, 116. 1978.
- SLAVIN, A. D. Our deciduous conifers. Am. Hort. **12**: 48–53. 1933. [*T. distichum*; excellent photographs of vars. *distichum* and *imbricarium*.]
- SMALL, J. K. A botanical expedition to the Big Cypress. Nat. Hist. **20**: 488–500. 1920.
- . The cypress, southern remnant of a northern fossil type. Jour. New York Bot. Gard. **32**: 125–135. 1931.
- STAHL, D. W., M. K. CLEAVELAND, & J. G. HEHR. North Carolina climate changes reconstructed from tree rings: A.D. 372 to 1985. [Based on living trees of *T. distichum* up to 1700 years old.]
- STERNITZKE, H. S. Bald cypress: endangered or expanding species. Econ. Bot. **26**: 130–134. 1972.
- TOMLINSON, P. B. The biology of trees native to tropical Florida. ix + 480 pp. Allston, Massachusetts. 1980. [*Taxodium*, 68–73; excellent illustrations of *T. distichum*. Differences between *T. distichum* and *T. ascendens* "are maintained in cultivated trees grown side by side."]
- VASIL, V., & R. K. SAHNI. Morphology and embryology of *Taxodium mucronatum* Tenore. Phytomorphology **14**: 369–384. 1964.
- VERNON, R. O. Cypress domes. Science **105**: 97–99. 1947.
- WATSON, F. D. A taxonomic study of pondcypress and baldcypress. 214 pp. Unpubl. Ph.D. dissertation, North Carolina State University, Raleigh. 1983.
- . The nomenclature of pondcypress and baldcypress (Taxodiaceae). Taxon **34**:

506–509. 1985. [*T. distichum* var. *imbricarium* is the correct name at the varietal level for pond cypress.]

WELCH, W. H. An ecological study of the bald cypress in Indiana. Proc. Indiana Acad. Sci. **41**: 207–213. 1931.

WHITFORD, L. A. A theory of the formation of cypress knees. Jour. Elisha Mitchell Sci. Soc. **72**: 80–83. 1956.

## 2. *Chamaecyparis* Spach, Hist. Nat. Veg. Phan. **11**: 329. 1841.

Pyramidal monoecious evergreen trees (rarely shrubs) with nodding leading shoots and a slender, spikelike crown from a thickened trunk. Branchlets slender, flattened (gradually becoming terete in later years if not shed), distichous and forming horizontal sprays. Bark reddish- [to grayish-]brown, irregularly ridged, often peeling in strips or scales. Wood soft [or hard], whitish to pinkish [to yellowish], aromatic [or not aromatic]. Leaves entire, aromatic when crushed; juvenile leaves whorled, linear-lanceolate, acuminate; adult leaves decussate, scalelike, dimorphic, the facial pair flattened, ovate to rhombic, acuminate to obtuse, with a central gland [or eglandular]; the lateral pair rounded or strongly keeled. Cones borne terminally on lateral branchlets, opening in early spring from buds formed the previous year; pollen and ovulate cones borne on separate branches. Pollen cones ovoid to oblong, quadrangular; microsporophylls ca. 8 to 12 (to 20), decussate; microsporangia 2 to 4 (to 6); pollen microverrucate, with obscure germinal aperture. Ovulate cones globose [to ellipsoid], maturing in 1 year [2 in *C. nootkatensis*], bearing 4 to 8 [rarely to 16] decussate, peltate scales; ovules bottle shaped, erect, [1 or] 2 [to 8] per scale. Maturing cones more or less erect, glaucous, ultimately red-brown. Seeds 1 or 2 [rarely to 8] per scale, ovate, with 2 broad lateral wings; cotyledons 2. Chromosome number  $2n = 22$ . LECTOTYPE SPECIES: *Chamaecyparis thyoides* (L.) BSP.; see Britton, N. Am. Trees, 102. 1908. (Greek name from *chamai*, on the ground, and *kyparissos*, cypress, alluding to the affinity of the genus to *Cupressus*, true cypress.)—FALSE CYPRESS, CYPRESS.

A genus of six species in North America and eastern Asia. Three species are native to eastern Asia and three (*Chamaecyparis thyoides* (L.) BSP., *C. nootkatensis* (D. Don) Spach, and *C. lawsoniana* (A. Murray) Parl.), to North America, with the latter two restricted to the Pacific Coast region. The Asian species are *C. formosensis* Matsum. in Taiwan, *C. obtusa* (Sieb. & Zucc.) Endl. in Japan and Taiwan, and *C. pisifera* (Sieb. & Zucc.) Endl. in Japan.

*Chamaecyparis* is generally thought to be closely related to the widespread Northern Hemisphere genus *Cupressus* L., which also has globose cones with peltate scales, and has sometimes been treated as a subgenus or section of the latter genus. It differs in having smaller ovulate cones (ca. 6–15 vs. ca. 15–40 mm in diameter), more heavily flattened branchlets, entire (vs. minutely ciliate) foliage leaves, and a shorter reproductive cycle (usually one vs. two years until ovulate-cone maturation). A small-coned species native to China has sometimes been treated as *Chamaecyparis funebris* (Endl.) Franco, but its biflavo-




FIGURE 1. *Chamaecyparis*. a-n, *C. thyoides*: a, branchlet tip, showing lateral and facial leaves,  $\times 5$ ; b, detail of branchlet tip with two terminal microsporangiate strobili,  $\times 12$ ; c, microsporophyll with two sporangia (abaxial view),  $\times 25$ ; d, microsporophyll (adaxial view), showing dehiscent sporangia,  $\times 25$ ; e, two ovulate cones at time of pollination,  $\times 12$ ; f, cone from "e." seen from above to show arrangement of cone scales and orthotropous ovules,  $\times 12$ ; g, one of lowermost pair of cone scales (adaxial view), showing two ovules at time of pollination,  $\times 12$ ; h, one of uppermost pair of cone scales (adaxial view) at time of pollination,  $\times 12$ ; i, young ovulate cone after pollination, the scales beginning to thicken and close,  $\times 6$ ; j, mature, unopened ovulate cone, showing fused bracts and scales,  $\times 3$ ; k, mature, open ovulate cone, three winged seeds visible on cone scale nearest viewer,  $\times 5$ ; l, winged seed, with micropyle facing upward,  $\times 6$ ; m, diagrammatic longitudinal section of mature seed, with embryo unshaded, gametophytic storage tissue dotted, seed coat hatched,  $\times 10$ ; n, embryo dissected from seed, showing two cotyledons,  $\times 10$ .

noid pattern supports its original placement in *Cupressus* (Gadek & Quinn, 1987).

*Chamaecyparis nootkatensis* is unusual in the genus in having less-flattened branchlets and a longer reproductive cycle; it is also divergent in its biflavonoid profile and tropolone composition (H. Erdtman & Norin; Gadek & Quinn, 1985). This species also is notable for producing intergeneric hybrids with *Cupressus* in cultivation. Leyland cypress ( $\times$  *Cupressocyparis Leylandii* (Jackson & Dallim.) Dallim. = *Chamaecyparis nootkatensis*  $\times$  *Cupressus macrocarpa* Gordon) apparently originated in England from spontaneous crosses in both directions (Osborn). More recently, hybrids between *Chamaecyparis nootkatensis* and *Cupressus glabra* Sudw. and *C. lusitanica* Miller, respectively, have also been reported from cultivated plants in England (Mitchell).

Our sole species, *Chamaecyparis thyoides* (including *C. Henryae* H. L. Li, *C. thyoides* var. *Henryae* (H. L. Li) Little), Atlantic white cedar, white cedar, swamp cedar, "juniper," occurs in swamps and wet woods near the Atlantic and Gulf coasts from southern Maine to northern Florida and westward to southeastern Mississippi. In the northern part of its range, it often occurs in pure stands, while in the south it frequently grows with bald cypress. It can be distinguished by its adult leaves that are usually glandular and not conspicuously whitened below, and by its branchlets that are irregularly arranged rather than held in the horizontal plane. In segregating the southern populations of the species (from Florida through Mississippi) as *C. Henryae*, H. L. Li cited a number of morphological differences (e.g., smoother bark with twisting ridges, lighter-colored microsporophylls, and less-glaucous ovulate cones), but the divergence between northern and southern populations is apparently clinal rather than abrupt (Hardin; E. L. Little, 1966). Thus, E. L. Little (1966) reduced *C. Henryae* to varietal status under *C. thyoides* and later (1979) placed it in synonymy.

Chromosome counts of  $2n = 22$  have been reported for four species of *Chamaecyparis* (Khoshoo, 1961; Kuo *et al.*; Sax & Sax); evidently no count has ever been made for *C. thyoides*. Natural interspecific hybridization has not been reported, but artificial crosses have been attempted in several combinations (Fukuhara; Yamamoto, 1981a, b). Meiotic irregularities have been reported in hybrids between *C. obtusa* and *C. pisifera* (Fukuhara), while a high percentage of nonviable seedlings was obtained in crosses of *C. Lawsoniana* and *C. pisifera* (Yamamoto, 1981a).

Among species of *Chamaecyparis*, significant differences have been reported in distributions of foliar terpenoids (Von Rudloff; Yatagai *et al.*) and heartwood tropolones (H. Erdtman & Norin), but more comprehensive population studies are needed. *Chamaecyparis nootkatensis* appears to be unique in the genus in having the tropolone nootkatin and the biflavonoid cupressuflavone, which are widespread in the genus *Cupressus* (H. Erdtman & Norin; Gadek & Quinn, 1985).

Most species of *Chamaecyparis* are utilized as ornamentals, with *C. Lawsoniana* (Port Orford cedar), *C. pisifera* (Sawara cypress), and *C. obtusa* (Hinoki cypress) being of particular importance. Hinoki cypress has religious significance in Japan and was often planted outside Shinto temples and used for

construction of temples and palaces (Wilson). The durable wood of the North American species has been valued for construction of boats and houses and for cooerage and shingles (Sargent, 1896, 1926). *Chamaecyparis thyoides* has historically been an important timber tree in the eastern United States, but large trees have been greatly depleted by logging (Jarvis; Tanglely). Submerged logs of the species are so resistant to decay that they have been "mined" from swamps (Jarvis).

## REFERENCES:

- Under family references see L. H. BAILEY; BEAN; BRITTON, 1908; DALLIMORE & JACKSON; H. ERDTMAN & NORIN; FITSCHEN; FLORIN, 1931, 1963; FOWELLS; GADEK & QUINN, 1985, 1987; GAUSSEN, 1968; GREGUSS, 1955, 1972; HARDIN; HART; KHOSHOO, 1961; KRÜSSMANN; KUO *et al.*, LEBRETON; LITTLE, 1971, 1979, 1980; OUDEN & BOOM; OWENS & SIMPSON; REHDER, 1940, 1949; ROUANE; SARGENT, 1896, 1926; SAX & SAX; SMALL; UENO, 1960b; VON RUDLOFF; WILSON; and YATAGAI *et al.*
- ANDERSEN, H. E. Silvical characteristics of Alaska-cedar (*Chamaecyparis nootkatensis*). U. S. Dep. Agr. Forest Serv. Alaska Forest Res. Center Pap. **11**, 10 pp. 1959.
- BANNAN, M. Abnormal xylem rays in *Chamaecyparis*. *Am. Jour. Bot.* **37**: 232-237. 1950. [Unusually wide rays in *C. Lawsoniana*, *C. nootkatensis*, and *C. thyoides*.]
- . The microscopic wood structure of North American species of *Chamaecyparis*. *Canad. Jour. Bot.* **30**: 170-187. 1952.
- BECK, G. F. Two newly discovered genera (*Tsuga* and *Chamaecyparis*) among the coniferous woods of the Tertiary. *Northwest Sci.* **18**: 9, 10. 1944.\*
- BELLING, A. J. Postglacial migration of *Chamaecyparis thyoides* (L.) B.S.P. (southern white cedar) in the northeastern United States. 220 pp. Unpubl. Ph.D. dissertation, New York University, New York. 1977.\*
- BRUSH, W. D. Knowing your trees: Atlantic whitecedar—*Chamaecyparis thyoides* (L.) Britton, Sterns & Poggenberg. *Am. Forests* **53**: 218, 219. 1947. [Uses, map, illustration.]
- BUCHHOLZ, J. T. The embryogeny of *Chamaecyparis obtusa*. *Am. Jour. Bot.* **19**: 230-238. 1932.
- CHENG, Y. S., & E. VON RUDLOFF. The volatile oil of the leaves of *Chamaecyparis nootkatensis*. *Phytochemistry* **9**: 2517-2527. 1970.
- CHESNOY, L. Sur l'origine paternelle des organites du proembryo du *Chamaecyparis Lawsoniana* A. Murr. (Cupressaceae). *Caryologia* **25**: 223-232. 1973.
- ELEUTERIUS, L. N., & S. B. JONES. A phytosociological study of white cedar in Mississippi. *Castanea* **37**: 67-74. 1972. [Includes notes on ecology and uses of *C. thyoides*.]
- FUKUHARA, N. Meiotic observations in the pollen mother cell of interspecific hybrid between *Chamaecyparis obtusa* and *C. pisifera*. *Jour. Jap. Forestry Soc.* **60**: 437-441. 1978. [Irregular meiotic pairing in the hybrids; both species have  $2n = 22$ .]
- GIANARDOLI, M. Recherches cytologiques sur la reproduction sexuée de *Chamaecyparis Lawsoniana*. *Compt. Rend. Acad. Sci. Paris* **254**: 4499-4501. 1962.
- HAYES, G. L. Silvical characteristics of the Port Orford cedar (*Chamaecyparis Lawsoniana*). U. S. Dep. Agr. Forest Serv. *Silvical Ser.* **7**, 11 pp. 1958.\*
- JARVIS, G. "Juniper," the versatile white cedar (*Chamaecyparis thyoides*). *Nature Mag.* **38**: 543, 544. 1945.
- KORSTIAN, C. F. Natural regeneration of southern white cedar. *Ecology* **5**: 188-191. 1924. [*C. thyoides*.]
- . Southern white cedar. U. S. Dep. Agr. *Tech. Bull.* **251**: 1-76. 1931. [*C. thyoides*.]
- LI, H. L. A new species of *Chamaecyparis*. *Morris Arb. Bull.* **13**: 43-46. 1962. [*C. Henryae* = *C. thyoides* var. *Henryae*.]



- LI, S.-J. Female reproductive organs of *Chamaecyparis*. *Taiwania* **17**: 27-39. 1972. [*C. formosensis*, *C. obtusa* var. *formosana*.]
- LITTLE, E. L., JR. Varietal transfers in *Cupressus* and *Chamaecyparis*. *Madroño* **18**: 161-167. 1966. [*C. thuyoides* var. *Henryae*.]
- LITTLE, S. Silvical characteristics of Atlantic white cedar. U. S. Dep. Agr. Forest Serv. Northeast. Forest Exper. Sta. Pap. **118**. iii + 16 pp. 1959.
- MCDONALD, C. B., & A. N. ASH. Structure and successional trends of an Atlantic white cedar (*Chamaecyparis thuyoides*) forest in Tyrrell County, North Carolina. (Abstract.) *ASB Bull.* **29**: 71. 1982. [Forms pure stands in swampy areas of the Carolinas and Virginia; these tend to succeed to *Nyssa-Taxodium* forest if left undisturbed.]
- MITCHELL, A. F. A note on two hybrid cypresses. *Jour. Roy. Hort. Soc.* **95**: 453, 454. 1970. [Spontaneous hybrids reported involving cultivated plants of *Chamaecyparis nootkatensis*, *Cupressus glabra*, and *Cupressus lusitanica*.]
- NEAL, O. M., JR. The status of *Chamaecyparis thuyoides* in Maine. *Rhodora* **42**: 343, 344. 1940.
- OSBORN, A. An interesting hybrid conifer: *Cupressocyparis Leylandii*. *Jour. Roy. Hort. Soc.* **66**: 54, 55. 1941. [*Cupressus macrocarpa* × *Chamaecyparis nootkatensis*.]
- OWENS, J. N., & M. MOLDER. Cone initiation and development before dormancy in yellow cedar (*Chamaecyparis nootkatensis*). *Canad. Jour. Bot.* **52**: 2075-2084. 1974.
- & ———. Pollination, female gametophyte, and embryo and seed development in yellow cedar (*Chamaecyparis nootkatensis*). *Ibid.* **53**: 186-199. 1975.
- , S. J. SIMPSON, & M. MOLDER. The pollination mechanism in yellow cypress (*Chamaecyparis nootkatensis*). *Canad. Jour. Forest Res.* **10**: 564-572. 1980.
- TANGLEY, L. Taking stock of white cedar wetlands. *Bioscience* **34**: 682-684. 1984.
- WARD, D. B. Southeastern limit of *Chamaecyparis thuyoides*. *Rhodora* **65**: 359-363. 1963. [Locally abundant in northwestern Florida, with distribution ending in Marion County.]
- YAMAMOTO, C. Xantha seedlings from interspecific crosses between *Chamaecyparis Lawsoniana* and *Chamaecyparis pisifera* as a remarkable case of hybrid inviability. (In Japanese; English summary.) *Jour. Jap. Forestry Soc.* **63**: 64-67. 1981a.
- . Possibilities of interspecific hybridization between *Chamaecyparis Lawsoniana* and some other *Chamaecyparis* species. (In Japanese; English summary.) *Ibid.* 311-319. 1981b.
- ZOBEL, D. B. Twig elongation patterns of *Chamaecyparis Lawsoniana*. *Bot. Gaz.* **144**: 92-103. 1983.

3. **Thuja** Linnaeus, Sp. Pl. 2: 1002. 1753; Gen. Pl. ed. 5. 435. 1754.

Evergreen, pyramidal, monoecious trees or sometimes shrubs; leading shoot erect; trunk often lobed and buttressed, sometimes dividing into 2 or more upright secondary stems. Bark reddish brown [to grayish], thin, fissured on older trees, peeling in irregular patches and fibrous shreds. Wood soft, pale, with light brown [to dark brown] aromatic heartwood. Branches horizontal at first, becoming ascending; branchlets slender, pendulous, forming flattened, frondlike, horizontal sprays, gradually becoming terete, the smaller leafy branchlets deciduous after several seasons. Foliage fragrant; juvenile leaves in spirally arranged whorls, linear-lanceolate, acuminate, spreading or reflexed, retained on adult plants of some cultivars; adult leaves decussately opposite, scalelike, closely imbricate (except on rapidly growing shoots), the facial leaves ovate, acute tipped (to ovate-lanceolate on rapidly growing shoots), with a central gland [or glandular], the lateral leaves folded over the facial ones, keeled. Buds small, naked, hidden by the leaves. Cones terminal and solitary, appearing in early spring; pollen and ovulate cones usually produced on dif-

ferent branchlets. Pollen cones nearly sessile, cylindrical or globose; microsporphylls ca. 4 to 6 [to 12], decussate, short stalked and more or less peltate, each with 2 to 4 microsporangia; pollen with obscure germinal aperture. Ovulate cones maturing in 1 season, terminal on short lateral branchlets, ovoid or oblong, with 8 to 12 imbricately arranged, oblong [to broadly ovate] scales, the central 4 to 6 fertile and bearing 2 (sometimes to 4) erect, bottle-shaped ovules; mature cones more or less erect; scales brownish, somewhat woody, with a minute [or more prominent] spine near the apex. Seeds (1 or) 2 (or 3) per scale, thin and flattened, with resin blisters in the thin seed coat, the membranaceous wings nearly encircling the whole seed, notched at the micropylar end; cotyledons 2. Chromosome number  $2n = 22$ . LECTOTYPE SPECIES: *Thuja occidentalis* L.<sup>7</sup> (From the Greek name of a resin-bearing conifer.)—ARBORVITAE, WHITE CEDAR.

A genus of five species, two in North America and three in Asia. *Thuja plicata* D. Don, western red cedar, is native to northwestern North America; *T. occidentalis* L. to the eastern deciduous forest area. *Thuja Standishii* (Gordon) Carr., *T. koraiensis* Nakai, and *T. sutchuensis* Franchet are native to portions of eastern Asia.

*Thuja occidentalis*, arborvitae, northern white cedar, white cedar, swamp cedar,  $2n = 22$ , is found from Nova Scotia westward to southeastern and central Manitoba, southward to the Great Lakes States and very locally south, barely reaching our region in mountainous areas of North Carolina and Tennessee. The species is common in the northern portion of its range, occurring over great areas of swampy forest land, where it forms largely impenetrable forests, as well as along rocky stream banks and drier limestone ridges, with best growth on neutral to alkaline substrates (Fernald; Fowells; Sargent, 1926). At the southern end of its distribution in western Virginia and Tennessee, arborvitae is less abundant, occurring only at higher elevations, usually on limestone or dolomitic cliffs. A number of floras (Britton, 1908; Coker & Totten; Little, 1980; Sargent, 1896, 1926) report the species from North Carolina, but there are apparently no natural populations remaining in the state (Clebsch; Radford *et al.*).

*Thuja occidentalis* differs from the other North American species (*T. plicata*) in usually having four rather than six fertile scales in the ovulate cone; these are also less prominently spine tipped. *Thuja plicata* is a larger tree, reaching 30–40(–70) (vs. 15–20(–25)) m in height, with more lustrous leaves that are more prominently whitened below.

The generic relationships of *Thuja* have not yet been determined with certainty. It has been suggested that it is most closely related to the monotypic eastern Asian genus *Thujopsis* Sieb. & Zucc. (Hart), which is similar in its tropolone profile (H. Erdtman & Norin) and embryogeny (Dogra, 1984) but differs in having subglobose ovulate cones with three to five (vs. usually two) seeds per scale and more spreading, hatchet-shaped lateral leaves. *Platycladus orientalis* (L.) Franco (*Biota orientalis* (L.) Endl., *Thuja orientalis* L.) has often

<sup>7</sup>The genus was effectively lectotypified when Spach (Hist. Nat. Veg. Phan. 11: 333, 1841) transferred the only other Linnaean species, *Thuja orientalis*, to *Platycladus* Spach.

been treated in the genus *Thuja* and may also be closely related, but is distinct from *Thuja* and *Thujopsis* in having fleshier immature cone scales, hard-coated, unwinged seeds, regularly occurring cleavage polyembryony, and vertically rather than horizontally oriented sprays of branchlets (Dallimore & Jackson; Singh & Oberoi).

Chromosome counts of  $2n = 22$  have been reported for three of the five species of *Thuja* (*T. occidentalis*, *T. plicata*, and *T. Standishii*) by Sax & Sax. All of the chromosomes were more or less isobranched in a cultivar of *T. occidentalis* studied by Mehra & Khoshoo.

Several preliminary comparisons have been made of terpenoid profiles from foliage of *Thuja* species (Banthorpe *et al.*; Von Rudloff, 1975; Yatagai *et al.*). *Thuja Standishii* is quite different from *T. occidentalis* and *T. plicata* in its monoterpene profile, while *Platycladus orientalis* is apparently quite similar to the latter two species based on the preliminary data of Banthorpe and colleagues. *Thuja plicata* shows very limited variation in leaf terpenoids and isozymes (Copes; Von Rudloff & Lapp; Von Rudloff *et al.*; Yeh) and apparently went through a genetic bottleneck during Pleistocene glaciation, while *T. occidentalis* seems to be more variable at the isozyme level (Walker).

*Thuja occidentalis* differs from three of the other species of the genus in having cupressuflavone present in its leaves, in addition to biflavonoids of the amentoflavone and hinokiflavone series (Gadek & Quinn, 1985).

The rate and pattern of root development in *Thuja occidentalis* were found to vary in relation to swampy versus calcareous substrate (Habeck). An increased rate of stem growth and greater wood strength were also found in plants growing on relatively dry limestone substrates by Harlow.

*Thuja occidentalis* and *T. plicata* are valued for their light, durable wood, which has been used for construction and to make fenceposts, railroad ties, and shingles. American Indian tribes have used the thick sapwood layers of both to make woven baskets and logs of *T. plicata* to make canoes and totem poles. The bark is rich in tannin, and the leaf oil has been used medicinally. *Thuja occidentalis* was one of the first North American trees cultivated in Europe, having been planted in Paris by about 1536. It was named arborvitae (tree of life) after tea brewed from the bark (which is rich in vitamin C) saved the crew of the French explorer Jacques Cartier from scurvy (Little, 1980). Several species of *Thuja* are cultivated as ornamentals, and diverse cultivars of *T. occidentalis* have been selected (Dallimore & Jackson; Krüssmann).

#### REFERENCES:

- Under family references see L. H. BAILEY; BANTHORPE *et al.*; BEAN; BRITTON, 1908; COKER & TOTTEN; DALLIMORE & JACKSON; DAGUILLON; DOGRA, 1984; G. ERDTMAN; H. ERDTMAN & NORIN; FITSCHEN; FLORIN, 1931, 1963; FOWELLS; GADEK & QUINN, 1985; GAUSSEN, 1968; GREGUSS, 1955, 1972; HARDIN; HART; HEGNAUER, 1962, 1986; KHOSHOO, 1961; KRÜSSMANN; LITTLE, 1971, 1980; MEHRA & KHOSHOO; OWENS & SIMPSON; PEIRCE; PHILLIPS; RADFORD *et al.*; REHDER, 1940, 1949; SARGENT, 1896, 1926; SAX & SAX; SINGH; SINGH & OBEROI; VON RUDLOFF, 1975; and YATAGAI *et al.*

AVITABILE, A. The eastern white cedar, *Thuja occidentalis* L., an early pollen source for honeybees. *Am. Bee Jour.* 122: 261. 1982.\*

- BANNAN, M. W. Vascular rays and adventitious root formation in *Thuja occidentalis* L. *Am. Jour. Bot.* **28**: 457–463. 1941a. [Unusually wide rays are the sites of initiation of adventitious roots.]
- . Wood structure in *Thuja occidentalis*. *Bot. Gaz.* **103**: 295–309. 1941b.
- . Ring width, tracheid size, and ray volume in the wood of *Thuja occidentalis* L. *Canad. Jour. Bot.* **32**: 466–479. 1954.
- . Girth increase in white cedar (*Thuja occidentalis*) stems of irregular form. *Ibid.* **35**: 425–434. 1957.
- CAPLENOR, D., & H. SPEIR. *Thuja occidentalis* L. on the Eastern Highland Rim in Tennessee. *Jour. Tennessee Acad. Sci.* **50**: 74, 75. 1975. [Distribution and ecology of *T. occidentalis* in Tennessee.]
- CLEBSCH, E. E. C. Was arbor vitae (*Thuja occidentalis* L.) native to North Carolina in historic times? *Am. Jour. Bot.* **76** (Suppl.): 157. 1989. [*T. occidentalis* apparently present in low numbers in the early 1900's but now extirpated.]
- & G. L. WALKER. Recent discoveries of range extensions of vascular plants associated with disjunct arbor vitae (*Thuja occidentalis* L.) in the Southeast. (Abstract.) *ASB Bull.* **33**: 69. 1986. [Native occurrence of arborvitae in North Carolina is undocumented.]
- COOK, P. L. A morphological comparison of two species of *Thuja*. Unpubl. Ph.D. dissertation, Univ. of Illinois, Champaign-Urbana. 1939.\*
- COPESE, D. L. Isoenzyme uniformity in western red cedar seedlings from Oregon and Washington. *Canad. Jour. Forest Res.* **11**: 451–453. 1981. [*T. plicata*.]
- FERNALD, M. L. Lithological factors limiting the range of *Pinus Banksiana* and *Thuja occidentalis*. *Rhodora* **21**: 41–67. 1919. [*T. occidentalis* largely restricted to basic soils; in outlying areas found on calcareous soils.]
- HABECK, J. R. White cedar ecotypes in Wisconsin. *Ecology* **39**: 457–463. 1958. [Local ecotypic differentiation in root development in *T. occidentalis* linked to substrate conditions.]
- HANDA, M. R. The life history of *Thuja occidentalis*. *Jour. Burma Res. Soc.* **16**: 214–219. 1926.\*
- HARLOW, W. M. The effect of site on the structure and growth of white cedar, *Thuja occidentalis* L. *Ecology* **8**: 453–470. *pl.* 7. 1927. [Stem growth is faster and wood is stronger and heavier in trees from limestone outcrops than in those from wetland sites.]
- LAND, W. G. A morphological study of *Thuja*. *Bot. Gaz.* **34**: 249–259. *pls.* 6–8. 1902. [Embryology of *T. occidentalis*.]
- MARTIN, P. C. A morphological comparison of *Biota* and *Thuja*. *Proc. Pennsylvania Acad. Sci.* **24**: 65–112. 1950. [*Platycladus* (*Biota*) *occidentalis* and *Thuja occidentalis* compared.]
- OWENS, J. N., & M. MOLDER. Sexual reproduction in western red cedar (*Thuja plicata*). *Canad. Jour. Bot.* **58**: 1376–1393. 1980.
- POLHEIM, F. *Thuja gigantea gracilis* Beissner—ein Haplont unter dem Gymnospermen. *Biol. Rundsch.* **6**: 84–86. 1968. [An unusual haploid variant of *T. plicata*.]
- VAARTAJA, O. Ecotype variation in photoperiodism of trees with special reference to *Pinus resinosa* and *Thuja occidentalis*. *Canad. Jour. Bot.* **40**: 849–856. 1962. [*T. occidentalis* is unusual in having growth rate little affected by day length.]
- VON RUDLOFF, E. Gas liquid chromatography of the terpenes. VI. The volatile oil of *Thuja plicata* Donn. *Phytochemistry* **1**: 195–202. 1962.
- & M. S. LAPP. Populational variation in the leaf oil terpene composition of western red cedar, *Thuja plicata*. *Canad. Jour. Bot.* **57**: 476–479. 1979. [Very little terpene variation among populations.]
- , ———, & F. C. YEH. Chemosystematic study of *Thuja plicata*: multivariate analysis of leaf oil terpene composition. *Biochem. Syst. Ecol.* **16**: 119–125. 1988.

[Discriminant analysis shows small differences between coastal and interior populations.]

- WALKER, G. L. Breeding systems and genetic variability in the population center and disjunct ranges of northern white cedar, *Thuja occidentalis*. (Abstract.) ASB Bull. 33: 49. 1986. [Substantial electrophoretic variability present within and among populations; both clonal and sexual reproduction occur within populations.]
- & E. C. CLEBSCH. The ecology of northern white cedar, *Thuja occidentalis* L., in its southern disjunct range. (Abstract.) ASB Bull. 31: 89. 1984. [New local stands in Tennessee, Kentucky, and Virginia found by using the distributions of other disjunct plant species.]
- WOLFE, F. Annual rings of *Thuja occidentalis* in relation to climatic conditions and movement of sand. Bot. Gaz. 93: 328–335. 1932.
- YEH, F. C. Isozyme variation of *Thuja plicata* (Cupressaceae) in British Columbia. Biochem. Syst. Ecol. 16: 373–377. 1988. [Low levels of variation seem to imply a Pleistocene genetic bottleneck.]

4. *Juniperus* Linnaeus, Sp. Pl. 2: 1038. 1753; Gen. Pl. ed. 5. 461. 1754.

Dioecious (rarely monoecious), evergreen, erect to prostrate shrubs, or pyramidal to open-crowned trees. Bark reddish-brown, usually thin and scaly, falling off in longitudinal strips [rarely thick and broken into plates]. Wood fragrant, close grained, with heartwood brownish to reddish-brown. Branches spreading or upright; branchlets rounded to nearly quadrangular or triangular, grooved and somewhat flattened. Leaves aromatic, entire or minutely denticulate; juvenile leaves in whorls of 3, linear-lanceolate to subulate, spreading; leaves of mature plants either also needlelike and in whorls of 3 (having the spreading portion linear-lanceolate, with rigidly pointed apex, eglandular, entire, abscising at the juncture with the stem [or retained on the decurrent leaf base], the abaxial surface concave and grooved, with 1 or 2 whitened stomatal bands) or in sect. *SABINA* mainly scalelike and decussately opposite (acute to acuminate or sometimes blunt tipped, closely appressed, imbricate, entire or minutely denticulate, glandular or eglandular, firmly attached to the decurrent base). Buds naked or covered with scalelike leaves, ovate to acute. Cones axillary or terminal on short branchlets from buds of the previous autumn. Pollen cones (microsporangiate strobili) solitary [or in clusters of 3 to 6 in *J. drupacea*], ovoid to oblong; microsporophylls decussate or ternate, (6 to) 10 to 20 per cone, ovate to peltate, entire to denticulate; microsporangia (2 or) 3 to 6 [rarely to 8] per sporophyll, globose, attached to the abaxial edge of the sporophyll; pollen with obscure germinal aperture. Ovulate cones ovoid to globose, maturing in 1, 2, or 3 years, subtended by several whorls of persistent scalelike bracts, with 3 to 8 [or 9] decussate or ternate fleshy scales, these alternating with or bearing on their inner surfaces 1 or 2 [rarely 3] erect ovules; mature ovulate cones berrylike, succulent or ultimately dry and fibrous, blue, blue-black [or reddish to brownish], resinous, with scales strongly fused and their suture lines seldom evident [rarely conspicuous], obscurely or conspicuously umbonate. Seeds 1 to 3 [rarely to 14] per cone, ovoid, terete or angled, wingless, often grooved or pitted by pressure from resin vesicles in the cone; seed coat thick and bony. Cotyledons 2 [to 6]. Chromosome number  $2n = 22$

(sometimes  $3n = 33$  [ $4n = 44$ ]). (Including *Sabina* Miller, *Arceuthos* Antoine & Kotschy.) LECTOTYPE SPECIES: *Juniperus communis* L.; see Britton, N. Am. Trees, 107. 1908. (Classical Latin name for juniper.)—JUNIPER, RED CEDAR.

The largest genus of Cupressaceae, with 50 or more species in North and Central America, Eurasia, and northern and eastern Africa, very widely distributed from the arctic to the mountains of the subtropics, and with one species, *Juniperus procera* Hochst., occurring on tropical mountains from 14°N to 12°S in eastern Africa (Florin, 1963). Junipers are often dominant plants in subdesert vegetation—for example, in the Great Basin area of the western United States. Of the 13 species native to the United States (Zanoni), *Juniperus Ashei* Buchh., *J. communis* L., and *J. virginiana* L. are native in the Southeast. Three sections are usually recognized in the genus, with sects. JUNIPERUS and SABINA (Miller) Spach represented by native species in our area. Section CARYOCEDRUS Endl. contains only a single species, *J. drupacea* Labill., native to Greece and Asia Minor and cultivated as an ornamental in Europe and the United States. This species, occasionally segregated in the monotypic genus *Arceuthos* Antoine & Kotschy, has very large (ca. 2–2.5 cm in diameter) and relatively woody ovulate cones with the coats of the three seeds connate, as well as clustered pollen cones, but is otherwise quite similar to sect. JUNIPERUS, having all leaves ternate and needlelike and the cones axillary.

Gaussen's (1967, 1968) informal classification treats the three sections as subgenera and divides them into ten sections (which were not formally described), largely on the bases of geography, cone color, number of seeds per cone, and presence or absence of teeth on the leaf margin. The genus has also been divided into eight informal species groups, generally following the "sections" of Gaussen, by Rushforth. Given the probability of repeated convergence for cone color and seed number, it is likely that several of the species groups in sect. SABINA are artificial, and no subsectional groups are recognized in Zanoni's treatment of the North and Central American species.

Section JUNIPERUS (sect. *Oxycedrus* Spach) (foliage leaves needlelike, ternate, eglandular, with blade jointed to the leaf base and abscising at the juncture with the stem; winter buds evident; cones solitary, axillary, with microsporophylls and cone scales ternate; ovulate cones one- to three-seeded, ripening in two or three years) comprises eight species (Dallimore & Jackson; Rushforth), primarily from northern or mountainous areas of North America, Eurasia, northern Africa, the Canary Islands, and the Azores. The only North American species is the very widespread *Juniperus communis* L. (*J. nana* Willd., nom. illeg.; *J. sibirica* Burgsd.), common juniper, ground juniper, mountain juniper,  $2n = 22$ , a prostrate or spreading shrub or sometimes a columnar to irregularly branched tree with a single white stomatal band generally wider than the adaxial leaf margins. It is native to much of northern North America, occurring south in the higher mountains to North and South Carolina and Georgia in the east and New Mexico and California in the west, and from coastal Greenland across Europe and northern and central Asia. Franco divided the species into four subspecies on the basis of habit and leaf morphology; he referred the eastern North American forms to subsp. *depressa* (Pursh) Franco (var. *depressa* Pursh)

because the stomatal band is narrower than the leaf margin. In our region the species is found primarily on barren rocky slopes and is a matted, prostrate shrub or very rarely a dwarfed tree (Coker & Totten).

Section *SABINA* Spach (adult leaves mostly scalelike and decussately opposite [or sometimes all ternate and needlelike], often with an abaxial gland, with the leaf base clearly decurrent on the stem and not jointed and abscising at the stem juncture; winter buds indistinct; cones terminal on elongating branchlets, usually solitary; ovulate cones maturing in one [or two] years, usually one- or two- [more rarely to 14-]seeded) comprises 40 or more species widely distributed in North and Central America and the Caribbean, southern and central Europe to eastern Asia, and northern and east-central Africa. The North American species have often been divided into entire- and denticulate-leaved groups (Gausson, 1967, 1968; Hall, 1952c; Rushforth; Zanoni & Adams, 1976). The majority of them are denticulate leaved, while *Juniperus horizontalis* Moench, *J. scopulorum* Sarg., *J. virginiana*, the Mexican *J. Blancoi* Martínez, and several Caribbean species have entire scale leaves and may form a natural group (Zanoni & Adams, 1976). The denticulate-leaved species in North America tend to occur in more xeric habitats (Hall, 1952c).

*Juniperus virginiana* L. (*Sabina virginiana* (L.) Antoine), eastern red cedar, red cedar, savin,  $2n = 22$  (rarely  $3n = 33$ ; Stiff), is named in allusion to its red heartwood. It is very widely distributed in the eastern half of the United States and southeastern Canada. It is a tree reaching 10–15(–30) m in height, with the trunk occasionally up to 1 m in diameter. In the Atlantic States the species often occurs on dry, gravelly slopes and rocky ridges, especially on calcareous soils. In Kentucky, Tennessee, northern Alabama, and Mississippi it covers great areas of rolling limestone hills, forming nearly pure stands of small bushy trees. The "cedar glades" in the Nashville Basin of Tennessee, noted for their unusual flora (Quarterman), are dominated by the species. Eastern red cedar is also often found in abandoned fields and along fence rows. In coastal areas of the eastern Gulf States, it often grows in deep swamps (where it tends to become a large tree), as well as on coastal sands. In southwestern Texas, Arkansas, and Louisiana it attains its largest size on rich alluvial bottomlands.

The populations of the southeastern Coastal Plain (from eastern North Carolina west to southeastern Texas) have often been treated as a separate species, *Juniperus silicicola* (Small) Bailey (*Sabina silicicola* Small; *Juniperus barbadensis* auct., non L.), but detailed comparisons of morphology and terpenoid chemistry by Adams (1986) indicate that they are better treated as var. *silicicola* (Small) Silba. Varietas *silicicola* has been distinguished as having shorter scale leaves, longer pollen cones, smaller ovulate cones, and more slender twigs, but there is considerable overlap in these characters, and multivariate comparisons fail to separate the geographic groups cleanly (Adams, 1986). Multivariate comparison of terpenoid profiles gives discrete but closely adjoining inland and coastal groups. Adams noted that coastal populations tend to have cinnamon-colored rather than brownish bark and a rounded rather than pyramidal crown. On the basis of both morphology and chemistry, populations from Texas and Louisiana, previously mapped as the coastal form by Little (1971), appear to fit into var. *virginiana* better than into var. *silicicola*.




FIGURE 2. *Juniperus*. a-j, *J. virginiana*: a, branchlets with only scale leaves, bearing mature ovulate cones,  $\times \frac{3}{4}$ ; b, branchlet with scale and needle leaves,  $\times \frac{3}{4}$ ; c, detail of branchlet with needle leaves, showing decurrent leaf bases,  $\times 5$ ; d, microsporangiate strobilus before shedding of pollen, subtended by numerous scale leaves,  $\times 5$ ; e, microsporophyll (abaxial view), showing dehiscent sporangia,  $\times 10$ ; f, branchlet with ovulate cone near time of pollination,  $\times 7$ ; g, cone scale (adaxial view) with 2 erect ovules near time of pollination,  $\times 10$ ; h, mature ovulate cone with fused cone scales,  $\times 3$ ; i, cross section of mature cone, only 2 seeds maturing—note resin vesicles outside seeds,  $\times 3$ ; j, seed, showing pits and ridges,  $\times 5$ . k-q, *J. communis*: k, branch, showing ternate leaves and axillary ovulate cones,  $\times \frac{3}{4}$ ; l, detail of abscised portion of leaf in adaxial view, showing broad stomatal band,  $\times 5$ ; m, microsporangiate strobilus after shedding of pollen,  $\times 5$ ; n, microsporophyll (abaxial view),  $\times 10$ ; o, short axillary shoot with young



The geographic distribution of *Juniperus virginiana* adjoins or partially overlaps those of several other entire-leaved species: *J. horizontalis* to the north, *J. scopulorum* to the west, and a taxonomically complex Caribbean group of species (Adams, 1983a; Adams & Hogge; Adams, Jarvis, Slane, & Zandoni) to the south. Hybridization with *J. horizontalis* and *J. scopulorum* has been suggested on the basis of morphological variation patterns (Fassett, 1944b, 1945b; Hall, 1952c; Schurtz). Terpenoid profiles are suggestive of past introgression from *J. scopulorum* into *J. virginiana* (Adams, 1983b; Comer *et al.*; Flake, Urbatsch, & Turner). Hybridization of *J. virginiana* and *J. horizontalis* on the edge of the Driftless Area in Wisconsin has been well documented by multivariate analyses of morphology and terpenoid chemistry, as well as electrophoretic-banding patterns of peroxidase enzymes (Palma-Otal *et al.*)

*Juniperus virginiana* is most similar in morphology to *J. scopulorum* and the Caribbean species complex. *Juniperus scopulorum* tends to differ from *J. virginiana* and the Caribbean species in having its cones mature in the second rather than the first year. Morton noted some variation for this character in *J. scopulorum* and suggested that it be treated as a variety of *J. virginiana*, but this view has not been accepted by most later authors. Other characters that have been used to separate these species (Fassett, 1944a, b; Hall, 1952c; Rehder, 1940) include the degree of overlap of the mature scale leaves (much greater in *J. virginiana*), the width of the leaf epidermal cells (greater in *J. scopulorum*), the shape of the leaf glands (more elongate in *J. scopulorum*), and the number of sporophylls per pollen cone (lower in *J. scopulorum*), although the variation patterns are complex in both and comparisons based on wide sampling are needed. The terpenoid distribution in the two taxa is distinctly bimodal and provides support for their treatment as separate species (Adams, 1983b; Comer *et al.*; Flake, Urbatsch, & Turner), partially intergrading in the northern and southern Great Plains.

As many as six species closely related to *Juniperus virginiana* have been recognized from the islands of the Caribbean (see discussions in Adams, 1983a, 1986; Adams & Hogge; Adams, Jarvis, Slane, & Zandoni), although some authors (Dallimore & Jackson; Silba) have placed most of these taxa in synonymy under *J. barbadensis* L. *Juniperus bermudiana* L., a rare species endemic to Bermuda, differs from *J. barbadensis* and *J. virginiana* in its stouter ultimate branches, averaging 1.5 mm or more in width. Preliminary studies (Adams, 1983a; Adams & Hogge) have indicated significant differences in terpenoid distribution among some of the Caribbean taxa and between the Caribbean taxa and the morphologically similar *J. virginiana* var. *silicicola*. A detailed monographic treatment of this group is much needed.

*Juniperus Ashei* Buchh. (*J. mexicana* Spreng., nom. illeg.), Ashe juniper, rock cedar, mountain cedar,  $2n = 22$ , occurs on upland limestone or dolomite outcrops in the Ozark Mountains of northwestern Arkansas, southwestern Mis-

---

ovulate cone at apex, showing 3 ovules near time of pollination,  $\times 10$ ; p, portion of branchlet with mature ovulate cone—note remnant leaf bases fused to larger stem,  $\times 3$ ; q, apical view of ovulate cone, showing suture lines between 3 fused cone scales,  $\times 3$ .

souri, and adjacent Oklahoma, in the Arbuckle Mountains of southern Oklahoma, in extreme southwestern Arkansas, and more broadly in west-central Texas (where it often forms dense stands on the Edwards Plateau) and northeastern Mexico. It is a small, bushy tree differing from *J. virginiana* in its more irregular or rounded branching habit, its minutely serrulate rather than entire leaves, and its typically rounded rather than elongate leaf glands. There have been a number of reports of hybridization or morphological intergradation between *J. Ashei* and *J. virginiana* (e.g., Hall, 1952a, c; 1955), but these have not been substantiated by subsequent comparison of terpenoid profiles (Adams, 1975a, 1977; Adams & Turner; Flake, Von Rudloff, & Turner). The disjunct northern populations of *J. Ashei*, well within the distribution of *J. virginiana*, are very similar in terpenoid profiles to populations of *J. Ashei* in the main portion of its range (Adams, 1975a). *Juniperus Ashei* is apparently most similar to the Mexican species *J. saltillensis* Hall in both morphology and terpenoid patterns (Adams, 1975a, 1977; Zanoni & Adams, 1976). The terpenoids of *J. Ashei* appear to represent a subset of those in the latter species, which may be its progenitor (Adams, Von Rudloff, Zanoni, & Hogge, 1980).

*Juniperus* is a very distinct genus in the Cupressaceae on the basis of its unique fleshy cones with fused cone scales; it has sometimes been placed in a monogeneric tribe or subfamily. Its affinities to other genera are not well established on the basis of morphology, but the genus is similar to *Cupressus* in its distribution of tropolones (H. Erdtman & Norin) and biflavonoids (Gadek & Quinn, 1985).

*Juniperus* has been the subject of an increasing number of detailed taxonomic studies using multivariate analyses of terpenoid chemistry, as well as morphology (see, for example, Adams, 1983a, b, 1986; Adams & Hogge; Adams, Von Rudloff, Hogge, & Zanoni; Adams, Von Rudloff, & Hogge; Zanoni & Adams, 1975, 1976), and preliminary revisions have been presented for the Mexican and Guatemalan (Zanoni & Adams, 1979) and North American (Zanoni) taxa of sect. SABINA. Species delimitation is often very difficult in the genus, and overall monographic treatment is much needed. Problems in distinguishing species are partially due to the relatively cryptic characters of leaves, stems, cones, and seeds used to separate them and to our poor knowledge of certain species. To a large degree, however, they are due to the complexity of variation within species and the limited divergence or convergence among them. Fassett's (1944a, b; 1945a, b) work on *J. virginiana*, *J. horizontalis*, and *J. scopulorum* illustrates the problems in attempting to discriminate among closely related species by the use of univariate comparisons of morphological characters—problems that have been obviated in part by multivariate analysis and the use of independent chemical data sets. Fassett found that quantitative variation within individual populations can be substantial, and that characters yielding statistically significant differences among species often show a considerable degree of overlap. Zones of past or present hybridization in the areas where the species meet also add to the taxonomic complexity.

As in the rest of the family, *Juniperus* most frequently has a chromosome number of  $2n = 22$ . Counts have been obtained for at least 23 species (see especially Hall, Mukherjee, & Crowley, 1973, 1979; Khoshoo, 1961; Mehra;

Mehra & Khoshoo; Sax & Sax) of which 19 are reported to be diploid or preponderantly diploid. Triploid or tetraploid plants have been found predominantly in horticultural variants (e.g., in *J. chinensis* L. and *J. squamata* Buch.-Ham.); their frequency in wild populations is unclear. Some species differ in karyotype; e.g., one chromosome pair is markedly heterobrachial in *J. horizontalis* and *J. procera*, while all of the chromosomes are more or less isobrachial in *J. communis*, *J. virginiana*, and several other species (Mehra; Mehra & Khoshoo; Mujoo & Dhar; Ross & Duncan).

As discussed by Lemoine-Sébastien (1968), evolution within the genus *Juniperus* has been marked by repeated reductions in the numbers of both cone-scale whorls and ovules, culminating in several species with a single apparently terminal ovule enveloped by one whorl of cone scales. Seeds with very hard coats contained in fleshy, "berrylike" cones are effective adaptations for seed dispersal by birds or sometimes mammals (Holthuijzen & Sharik, 1984, 1985; Phillips). As in a number of other groups of conifers, animal dispersal of seeds is coupled with a dioecious breeding system (Givnish).

Several species of junipers (e.g., *Juniperus virginiana*) are hosts for cedar-apple rust (*Gymnosporangium* spp.), which produces conspicuous gall-like growths on the plant (illustrated in Coker & Totten) and is a serious pathogen of cultivated apples and other woody Rosaceae.

The wood of *Juniperus* is fragrant, very durable, and little damaged by insects. Wood and bark of several North American species have been found to be very effective termiticides (Adams, McDaniel, & Carter). The wood of *J. virginiana* has been much used for pencils, although incense cedar (*Calocedrus decurrens* (Torrey) Florin) is now much more widely employed for this purpose because of heavy exploitation of red cedar (Hemmerly). Red cedar wood has been widely used for fenceposts and furniture, especially moth-resistant cedar chests for storage of clothing. In the western United States junipers are also highly valued for their aromatic firewood. The essential oil (cedarwood oil) from the heartwood of *Juniperus* species has been widely utilized in compounding fragrances for soaps, perfumes, and industrial uses, as well as in microscopy as a mountant (Adams, 1987; Hemmerly). Leaf or fruit oils of *Juniperus* have been used medicinally and can possess powerful diuretic properties. Many species of junipers are grown as ornamentals, and a large number of habit and color variants have been selected, particularly in *J. chinensis*, *J. communis*, and *J. virginiana* (Dallimore & Jackson; Krüssmann; Ouden & Boom). Juniper "berberics" from *J. communis* are used as flavoring agents in cooking and in the production of the alcoholic beverage gin (the name shortened from Dutch *junever*, traceable back to Latin *juniperus*).

#### REFERENCES:

- Under family references see BAILEY; BEAN; BRITTON, 1908; COKER & TOTTEN; DALLIMORE & JACKSON; G. ERDTMAN; H. ERDTMAN & NORIN; FITSCHEN; FLORIN, 1931, 1963; GADEK & QUINN, 1985; GAUSSEN, 1968; GIVNISH; GREGUSS, 1955, 1972; HARDIN; HART; HEGNAUER, 1962, 1986; KHOSHOO, 1961; KRÜSSMANN; LITTLE, 1971, 1980; MEHRA & KHOSHOO; OUDEN & BOOM; OWENS & SIMPSON; REHDER, 1940, 1949; RUSHFORTH; SARGENT, 1896, 1926; SAX & SAX; SILBA; SINGH; UENO, 1960b; and VON RUDLOFF.

- ADAMOVICH, E. I. Resin receptacles of *Juniperus communis* L. (In Russian.) Lesn. Zhur. **4**: 159–161. 1961.\*
- ADAMS, R. P. Seasonal variation of terpenoid constituents in natural populations of *Juniperus Pinchotii* Sudw. Phytochemistry **9**: 397–402. 1970.
- . Chemosystematic and numerical studies of natural populations in *Juniperus Pinchotii* Sudw. Taxon **21**: 407–427. 1972. [*J. Pinchotii* and *J. monosperma* compared.]
- . Reevaluation of the biological status of *Juniperus Deppeana* var. *Sperryi* Correll. Brittonia **25**: 284–289. 1973. [Terpenoids of *J. Deppeana*, *J. flaccida*, and *J. Pinchotii*.]
- . Gene flow versus selection pressure and ancestral differentiation in the composition of species; analysis of populational variation of *Juniperus Ashei* Buch. using terpenoid data. Jour. Molecular Evol. **5**: 177–185. 1975a.
- . Numerical chemosystematic studies of infraspecific variation in *Juniperus Pinchotii*. Biochem. Syst. Ecol. **3**: 71–74. 1975b.
- . Chemosystematics—analysis of populational differentiation and variability of ancestral and recent populations of *Juniperus Ashei*. Ann. Missouri Bot. Gard. **64**: 184–209. 1977.
- . Diurnal variation in the terpenoids of *Juniperus scopulorum* (Cupressaceae)—summer versus winter. Am. Jour. Bot. **66**: 986–988. 1979. [Diurnal and day-to-day variation within trees is lower in winter when plants are less active metabolically.]
- . The effects of gases from a burning coal seam on morphological and terpenoid characters in *Juniperus scopulorum* (Cupressaceae). Southwest. Nat. **27**: 279–286. 1982. [A local columnar form of *J. scopulorum* is environmentally induced; hybridization with *J. horizontalis* in North Dakota is indicated by multivariate comparisons.]
- . The junipers (*Juniperus*; Cupressaceae) of Hispaniola: comparisons with other Caribbean species and among collections from Hispaniola. Moscosoa **2**: 77–89. 1983a.
- . Intraspecific terpenoid variation in *Juniperus scopulorum*: evidence for Pleistocene refugia and recolonization in western North America. Taxon **32**: 30–46. 1983b.
- . Geographic variation in *Juniperus silicicola* and *J. virginiana* of the southeastern United States; multivariate analyses of morphology and terpenoids. *Ibid.* **35**: 61–75. 1986. [*J. silicicola* is best treated as a variety of *J. virginiana*.]
- . Investigation of *Juniperus* species of the United States for new sources of cedarwood oil. Econ. Bot. **41**: 48–54. 1987. [Composition of volatile oils from the heartwood of ten species.]
- & A. HAGERMAN. A comparison of the volatile oils of mature versus young leaves of *Juniperus scopulorum*: chemosystematic significance. Biochem. Syst. Ecol. **4**: 75–79. 1976. [Hydrocarbon terpenoids show highest levels in younger leaves, oxygenated terpenoids in older ones.]
- & ———. Diurnal variation in the volatile terpenoids of *Juniperus scopulorum* (Cupressaceae). Am. Jour. Bot. **64**: 278–285. 1977.
- & L. HOGGE. Chemosystematic studies of the Caribbean junipers based on their volatile oils. Biochem. Syst. Ecol. **11**: 85–89. 1983.
- , C. E. JARVIS, V. SLANE, & T. A. ZANONI. Typification of *Juniperus barbadensis* L. and *J. bermudiana* L. and rediscovery of *J. barbadensis* from St. Lucia, BWI (Cupressaceae). Taxon **36**: 441–445. 1987. [Typification of *J. barbadensis* and *J. bermudiana* is clarified; these are apparently distinct species with narrow ranges in the Caribbean.]
- , C. A. MCDANIEL, & F. L. CARTER. Termiticidal activities in the heartwood, bark/sapwood and leaves of *Juniperus* species from the United States. Biochem. Syst. Ecol. **16**: 453–456. 1988.

- & B. L. TURNER. Chemosystematic and numerical studies of natural populations of *Juniperus Ashei* Buch. *Taxon* **19**: 728–751. 1970.
- , E. VON RUDLOFF, & L. HOGGE. Chemosystematic studies of the western North American junipers based on their volatile oils. *Biochem. Syst. Ecol.* **11**: 189–193. 1983.
- , ———, ———, & T. A. ZANONI. The volatile constituents of *Juniperus Blancoi* and its affinities with other entire leaf margin junipers of North America. *Jour. Nat. Prod.* **44**: 21–26. 1981. [*J. Blancoi* compared to *J. horizontalis*, *J. scopulorum*, and *J. virginiana*.]
- , ———, T. A. ZANONI, & L. HOGGE. The terpenoids of an ancestral/advanced species pair of *Juniperus*. *Biochem. Syst. Ecol.* **8**: 35–37. 1980. [*J. Ashei* and *J. saltillensis* have similar profiles, with a more restricted set of compounds in the former.]
- , ———, ———, & ———. The south-western USA and northern Mexico one-seeded junipers: their volatile oils and evolution. *Ibid.* **9**: 93–96. 1981. [*J. erythrocarpa*, *J. monosperma*, *J. Pinchotii*.]
- AFANASIEV, M., & M. CRESS. Changes within the seeds of *Juniperus scopulorum* during the processes of after-ripening and germination. *Jour. Forestry* **40**: 798–801. 1942.
- AGRAMONT, F., R. BUSKING, J. MITCHELL, & E. ENZINGER. The red cedar. *Missouri Bot. Gard. Bull.* **36**: 86–92. 1948. [Variation of *J. virginiana* in the St. Louis area.]
- ALEKSANDROVSKY, E. S. Biology of blooming and fruiting of *Juniperus turcomanica* Fedtsch. (In Russian; English summary.) *Lesovedenie* **1972**(3): 76–84. 1972.
- ANDRÉ, D. Contribution à l'étude morphologique du cône femelle de quelques gymnospermes (Cephalotaxacées, Juniperoidées, Taxacées). *Nat. Monspel. Bot.* **8**: 3–35. 1956.
- ANTOINE, F. Die Cupressineen-Gattungen: *Arceuthos*, *Juniperus* and *Sabina*. 71 pp. Vienna. 1857.\*
- AREND, J. L. An early eastern red cedar plantation in Arkansas. *Jour. Forestry* **45**: 358–360. 1947. [*J. virginiana*.]
- AYAZ, M. Anatomy of juniper (*Juniperus excelsa*) seed. *Pakistan Jour. Forestry* **30**: 99–101. 1980.
- BERTSCH, A. Untersuchungen an rezenten und fossilen Pollen von *Juniperus*. *Flora* **150**: 503–513. *pl. 12*. 1961.
- BIFOSS, C. G. The water conductivity and growth habits of *Juniperus horizontalis* Moench and *Juniperus virginiana* L. *Ecology* **28**: 281–289. 1947. [No appreciable differences between species in water conductivity of the stem, but stem growth of *J. virginiana* is much higher under favorable conditions.]
- BOYD, H. Eastern red cedar (*Juniperus virginiana* L.)—a list of references. U. S. Dep. Agr. Library, Louisiana Branch, New Orleans. 5 pp. 1951.\*
- BUCHHOLZ, J. T. The Ozark white cedar. *Bot. Gaz.* **90**: 326–332. 1930. [*Juniperus Ashei* described and distinguished from *J. monosperma*.]
- CHATURVEDI, M. Studies on the pollen grains of *Juniperus* L. *Curr. Sci. Bangalore* **50**: 548, 549. 1981.\*
- CHESNOY, L. Sur le développement des cônes femelles du *Juniperus communis* L., dans la région parisienne, de la pollinisation à la graine. *Compt. Rend. Acad. Sci. Paris, D.* **262**: 2018–2021. *pl. 1*. 1966.
- . Nature et évolution des formations dites "astéroïdes" de la cellule centrale de l'archégone du *Juniperus communis* L. Étude en microscopie photonique et électronique. *Ibid.* **264**: 1016–1019. *pls. 1–6*. 1967.
- CIAMPI, C. Processi post-fecondativi nel genere *Juniperus*. Osservazioni in *Juniperus Oxycedrus* L. e *Juniperus macrocarpa* S. S. *Caryologia* **11**: 334–347. *pls. 17–20*. 1959.
- COCKER, H. R. Junipers of the Mediterranean area. *Arb. Bull.* **20**: 15, 16, 35. 1957.
- COLLINGWOOD, G. H. Eastern red cedar. *Am. Forests* **44**: 30, 31. 1938. [*J. virginiana*.]

- COMER, C. W., R. P. ADAMS, & D. F. VAN HAVERBEKE. Intra- and interspecific variation of *Juniperus virginiana* and *J. scopulorum* seedlings based on volatile oil composition. *Biochem. Syst. Ecol.* **10**: 297-306. 1982. [Separate species status and probable past hybridization indicated by multivariate comparisons.]
- CUCCHI, C. C. Indagine geobotanica sui ginepri europei. *Delpinoa* **11**: 171-222. pls. 1-7. 1958. [Morphology and distribution of *J. communis* and *J. Sabina*; key to European junipers.]
- DOGRA, P. D., & S. TANDON. Observations on the embryology of *Juniperus procera* Hochst. *Glimpses Pl. Res.* **6**: 114-124. figs. 1-53. 1984. [Early embryogeny compared to that of other species of *Juniperus*.]
- DUHOUX, E. Évolution structurale de la paroi du grain de pollen du *Juniperus communis* L. (Cupressacées), cultivé in vitro, au cours de la phase d'hydratation. *Compt. Rend. Acad. Sci. Paris, D.* **274**: 2767-2770. pls. 1-3. 1972.
- . Les déplacements du noyau végétatif dans le tube pollinique du *Juniperus communis* L. (Cupressacées) cultivé in vitro. *Rev. Cytol. Biol. Veg.* **4**: 311-330. 1981.\*
- ENGELMANN, G. The American junipers of the section *Sabina*. *Trans. St. Louis Acad. Sci.* **3**: 583-592. 1877. [Nine species recognized.]
- EVANS, G. E., & H. P. RASMUSSEN. Chromosome counts in three cultivars of *Juniperus* L. *Bot. Gaz.* **132**: 259-262. 1971. [*J. horizontalis*, *J. Sabina*,  $2n = 22$ ; *J. chinensis*,  $3n = 33$ .]
- FASSETT, N. C. The validity of *Juniperus virginiana* var. *crebra*. *Am. Jour. Bot.* **30**: 469-477. 1943. [The northern var. *crebra* is generally more narrow crowned than var. *virginiana*; degree of acuteness of the leaves and degree of seed pitting show little consistent difference.]
- . *Juniperus virginiana*, *J. horizontalis*, and *J. scopulorum*. I. The specific characters. *Bull. Torrey Bot. Club* **71**: 410-418. 1944a. II. Hybrid swarms of *J. virginiana* and *J. scopulorum*. *Ibid.* 475-483. 1944b. [Individuals with intermediate character states found in areas of geographic overlap.] III. Possible hybridization of *J. horizontalis* and *J. scopulorum*. *Ibid.* **72**: 42-46. 1945a. [Where the two species occur together, *J. scopulorum* tends to approach *J. horizontalis* in several characters; a depressed form apparently intermediate between the two species is described as *J. scopulorum* var. *patens* Fassett.] IV. Hybrid swarms of *J. virginiana* and *J. horizontalis*. *Ibid.* 379-384. 1945b. [Where the ranges of the two species overlap, intermediates (described as *J. virginiana* var. *ambigens* Fassett) are found.] V. Taxonomic treatment. *Ibid.* 480-482. 1945c.
- FERGUSON, E. R. Eastern red cedar: an annotated bibliography. U. S. Dep. Agr. Forest Serv. Res. Pap. **SO-64**. 21 pp. 1970.
- FLAKE, R. H., L. URBATSCH, & B. L. TURNER. Chemical documentation of allopatric introgression into *Juniperus*. *Syst. Bot.* **3**: 129-144. 1978. [Terpenoid profiles suggest introgression from *J. scopulorum* to *J. virginiana*.]
- , E. VON RUDLOFF, & B. L. TURNER. Quantitative study of clinal variation in *Juniperus virginiana* using terpenoid data. *Proc. Natl. Acad. Sci. U. S. A.* **64**: 487-494. 1969. [Clinal variation from northeast to southwest reported, with no evidence of hybridization with *J. Ashei*.]
- , ———, & ———. Confirmation of a clinal pattern of chemical differentiation in *Juniperus virginiana* from terpenoid data obtained in successive years. *Recent Adv. Phytochem.* **6**: 215-228. 1973.\*
- FRANCO, J. DO A. Taxonomy of the common juniper. *Bol. Soc. Brot.* **32**: 101-120. 1962. [Four geographic subspecies of *J. communis* recognized.]
- FRETZ, T. A. Effect of photoperiod and nitrogen on the composition of foliar monoterpenes of *Juniperus horizontalis* Moench cv. *Plumosa*. *Jour. Am. Soc. Hort. Sci.* **101**: 611-613. 1976. [Increased photoperiod altered the relative concentration of several terpenic compounds.]

- GALL, E. C. *Juniperus* at the Morris Arboretum. *Morris Arb. Bull.* **13**: 3-10. 1962. [Keys and notes for 13 species; illustrations.]
- GAUSSEN, H. La classification des genévriers (*Juniperus*). *Compt. Rend. Acad. Sci. Paris, D.* **265**: 954-957. 1967.
- GROOTENDORST, H. J. *Juniperus communis* L. (In Dutch.) *Dendroflora* **5**: 29-34. 1968.\*
- GROVES, G. R. The Bermuda cedar. *Unasylya* **9**: 169-172. 1955. [Utilization of *J. bermudiana*.]
- HALL, M. T. A hybrid swarm in *Juniperus*. *Evolution* **6**: 347-366. 1952a. [*J. Ashei* and *J. virginiana* in the Arbuckle Mountains of Oklahoma; see also later chemical comparisons (e.g., FLAKE, VON RUDLOFF, & TURNER), which do not support the hypothesis of interspecific hybridization.]
- . Variation in native junipers. *Cranbrook Inst. Sci. News Letter* **21**: 62-64. 1952b.
- . Variation and hybridization in *Juniperus*. *Ann. Missouri Bot. Gard.* **39**: 1-64. 1952c. [Morphological evidence for purported hybridization between *J. Ashei* and *J. virginiana*.]
- . Nomenclatural notes concerning *Juniperus*. *Rhodora* **56**: 169-177. 1954. [Comparison of *J. Ashei* and *J. monticola*.]
- . Comparison of juniper populations on an Ozark glade and old fields. *Ann. Missouri Bot. Gard.* **42**: 171-194. 1955. [Variation in *J. virginiana*.]
- . Know your cultivated junipers. *Arb. Bull.* **20**: 10-12. 1957.
- . A new species of *Juniperus* from Mexico. *Fieldiana Bot.* **34**: 45-53. 1971. [*J. saltillensis*.]
- & C. J. CARR. Variability of *Juniperus* in the Palo Duro Canyon of western Texas. *Southwest. Nat.* **13**: 75-98. 1968.
- , J. F. McCORMICK, & G. G. FOGG. Hybridization between *J. Ashei* and *J. Pinchotii* in southwestern Texas. *Butler Univ. Bot. Stud.* **14**: 9-28. 1962.\*
- , A. MUKHERJEE, & W. R. CROWLEY. Chromosome counts in cultivated junipers. *Jour. Arnold Arb.* **54**: 369-376. 1973. [Diploid counts (all  $2n = 22$ ) obtained for seven species, including *J. communis* and *J. virginiana*; tetraploid counts for two varieties of *J. chinensis* and one of *J. squamata*.]
- , ———, & ———. Chromosome numbers of cultivated junipers. *Bot. Gaz.* **140**: 364-370. 1979. [Counts for ten species, including *J. communis* ( $2n = 22$ ) and *J. virginiana* ( $2n = 22$ ,  $3n = 33$ ), with the triploid cultivar intermediate to *J. chinensis* in morphology.]
- HARPER, R. M. The diverse habitats of the eastern red cedar and their interpretation. *Torrey* **12**: 145-154. 1912. [*J. virginiana* largely absent from fire-controlled habitats.]
- HEMMERLY, T. E. Economic uses of eastern red cedar. *Econ. Bot.* **24**: 39-41. 1970. [*J. virginiana*.]
- HOLTHUIJZEN, A. M. A., & T. L. SHARIK. Seed longevity and mechanisms of regeneration of eastern red cedar (*Juniperus virginiana*). *Bull. Torrey Bot. Club* **111**: 153-158. 1984.
- & ———. The avian dispersal system of eastern red cedar (*Juniperus virginiana*). *Canad. Jour. Bot.* **63**: 1508-1515. 1985.
- IRVING, R. S. A chromosome count for *Juniperus Ashei* (Cupressaceae) and additional numbers for *Hedeoma* (Labiatae). *Sida* **8**: 312, 313. 1980. [ $2n = 22$  for *J. Ashei*.]
- JACK, J. G. Fructification of *Juniperus*. *Bot. Gaz.* **18**: 369-375. pl. 33. 1893. [Ovulate cones of *J. virginiana* mature in one year, of *J. horizontalis* in two years, of *J. communis* in three years.]
- JOHNSON, T. N. Longevity of stored juniper seeds. *Ecology* **40**: 487, 488. 1959. [Seeds of *J. Deppeana*, *J. monosperma*, and *J. osteosperma* can survive long periods in dry storage.]
- KAEISER, M. Microscopic anatomy of the wood of three species of *Juniperus*. *Trans. Illinois Acad. Sci.* **43**: 46-50. 1950.

- . Microstructure of the wood of *Juniperus*. Bot. Gaz. **115**: 155–162. 1953. [Most species of sect. SABINA have large intercellular spaces between the tracheids; these are absent in the other sections.]
- KELLEY, W. A., & R. P. ADAMS. Seasonal variation of isozymes in *Juniperus scopulorum*: systematic significance. Am. Jour. Bot. **64**: 1092–1096. 1977. [Some bands are present only seasonally.]
- . Analysis of isozyme variation in natural populations of *Juniperus Ashei*. Rhodora **80**: 107–134. 1978.
- KLEIN, S. Cedar species: their geographical distribution and uses. Am. Perfumer Essent. Oil Rev. **51**: 137–140. 1948.\* [*Juniperus*.]
- KLEIN, W. M. Cotyledon variations in *Juniperus occidentalis* Hook. Aliso **4**: 129. 1958. [Geographic differences in number of cotyledons.]
- LEBRETON, P., & S. THIVEND. Sur une sous-espèce du genévrier de Phénicie, *Juniperus phoenicea* L., définie à partir de critères biochimiques. Nat. Monspel. Bot. **47**: 1–12. 1981. [Two subspecies are separated on the basis of high vs. low levels of proclaphinidin.]
- LEMOINE-SÉBASTIAN, C. Anatomie des plantules de quelques *Juniperus*. Trav. Lab. For. est. Toulouse, Tome I, Vol. VI, Art. XXI: 1–12. pl. 5. 1964.
- . Appareil reproducteur mâle des *Juniperus*. *Ibid.*, Art. XXIV: 1–35. 1967. [Pollen-cone morphology, including that of *J. communis* and *J. virginiana*.]
- . L'inflorescence femelle des Junipereae: ontogenèse, structure, phylogénèse. *Ibid.*, Tome I, Vol. VII, Art. V: 1–460. pls. 229–247. 1968. [Detailed discussion of ovulate-cone development in 21 species, including *J. communis* and *J. virginiana*.]
- MARTÍNEZ, M. Los *Juniperus* mexicanos. Anal. Inst. Biol. Méx. **17**: 1–121. 1946. [A new classification of the Mexican taxa of sect. *Sabina* provided.]
- MASSEY, A. B. Ecology of the red cedar, *Juniperus virginiana*. (Abstract.) ASB Bull. **11**: 261. 1954.
- MASTERS, M. T. Bermuda juniper and its allies. Jour. Bot. (London) **37**: 1–11. 1899.
- MATHEWS, A. C. The morphological and cytological development of the sporophylls and seed of *Juniperus virginiana* L. Jour. Elisha Mitchell Sci. Soc. **55**: 7–62. pls. 1–9. 1939.
- MCCORMICK, J. F., & R. B. PLATT. Ecotypic differentiation in southeastern *Juniperus*. (Abstract.) ASB Bull. **9**: 30. 1962. [Purported introgression between *J. Ashei* and *J. virginiana* discussed.]
- MEHRA, P. N. Conifers of the Himalayas with particular reference to the *Abies* and *Juniperus* complexes. Nucleus **19**: 123–139. 1976. [Morphology and distribution of nine species of *Juniperus*; new chromosome counts for *J. Fargesii*, *J. pseudosabina* (both  $2n = 22$ ), and *J. Wallichiana* ( $4n = 44$ ).]
- MINCKLER, L. S., & R. A. RYKER. Color, form, and growth variations in eastern redcedar. Jour. Forestry **57**: 347–349. 1959. [Common garden experiments with *J. virginiana*.]
- MORTON, C. V. Notes on *Juniperus*. Rhodora **43**: 344–348. 1941.
- MUJOO, S., & G. I. DHAR. Cytology of *Juniperus communis* var. *nana* Syme. Nucleus **24**: 46–48. 1982. [Chromosome number  $2n = 22$ ; all chromosomes with median or submedian centromeres.]
- NICHOLS, G. E. A morphological study of *Juniperus communis* var. *depressa*. Beih. Bot. Centralbl. **25**: 201–241. 1910.
- OTTLEY, A. M. The development of the gametophytes and fertilization in *Juniperus communis* and *Juniperus virginiana*. Bot. Gaz. **48**: 31–46. pls. 1–4. 1909.
- PACK, D. A. After-ripening and germination of *Juniperus* seeds. Bot. Gaz. **71**: 32–60. 1921. [*J. communis*, *J. virginiana*.]
- PALMA-OTAL, M., W. S. MOORE, R. P. ADAMS, & G. R. JOSWIAK. Morphological, chemical, and biogeographical analyses of a hybrid zone involving *Juniperus virginiana* and *J. horizontalis* in Wisconsin. Canad. Jour. Bot. **61**: 2733–2746. 1983. [Multi-



- variate analyses of morphology and terpene chemistry and peroxidase banding patterns used to document hybridization.]
- PHILLIPS, F. J. The dissemination of junipers by birds. *Forestry Quart.* **8**: 60–73. 1910.
- POWELL, R. A., & R. P. ADAMS. Seasonal variation in the volatile terpenoids of *Juniperus scopulorum* (Cupressaceae). *Am. Jour. Bot.* **60**: 1041–1050. 1973.
- QUARTERMAN, E. Major plant communities of Tennessee cedar glades. *Ecology* **31**: 234–254. 1950.
- ROSS, J. G., & R. E. DUNCAN. Cytological evidences of hybridization between *Juniperus virginiana* and *J. horizontalis*. *Bull. Torrey Bot. Club* **76**: 414–429. 1949. [Karyotypic variation and meiotic irregularities in areas of apparent hybridization.]
- SAN FELICIANO, A., M. MEDARDE, J. L. LOPEZ, J. M. MIGUEL DEL CORRAL, P. PUEBLA, & A. F. BARRERO. Terpenoids from leaves of *Juniperus thurifera*. *Phytochemistry* **27**: 2241–2248. 1988. [Diverse diterpenoids of the labdane, pimarane, and abietane types were isolated from the leaves of *J. thurifera*.]
- SARGENT, C. S. Notes on cultivated conifers. IV. *Garden Forest* **10**: 420, 421. 1897. [*J. scopulorum* and *J. virginiana* distinguished.]
- SCHURTZ, R. H. A taxonomic analysis of a triparental hybrid swarm in *Juniperus* L. 90 pp. Unpubl. Ph.D. dissertation, University of Nebraska, Lincoln. 1971.\* [*J. horizontalis*, *J. scopulorum*, *J. virginiana*.]
- SÉBASTIAN, C. Essais de germination de quatre espèces du genre *Juniperus*. *Bull. Soc. Sci. Nat. Phys. Maroc* **38**: 115–122. 1958a.
- . Sur la phyllotaxie de *Juniperus phoenicea*. *Ibid.* 187–194. 1958b.
- STIFF, M. L. A naturally occurring triploid juniper. (Abstract.) *Virginia Jour. Sci.* **2**: 317. 1951. [*J. virginiana* from Virginia.]
- TATRO, V. E., R. W. SCORA, F. C. VASEK, & J. KUMAMOTO. Variation in the leaf oils of three species of *Juniperus*. *Am. Jour. Bot.* **60**: 236–241. 1973. [*J. californica*, *J. occidentalis*, *J. osteosperma*.]
- VAN HAVERBEKE, D. F. A population analysis of *Juniperus* in the Missouri River Basin. *Univ. Nebraska Studies* **38**: 1–82. 1968.\* [Variation of *J. scopulorum* and *J. virginiana* in the northern Great Plains.]
- VAN MELLE, P. J. *Juniperus texensis* sp. nov.—West-Texas juniper in relation to *J. monosperma*, *J. Ashei* et al. *Phytologia* **4**: 26–35. 1952.
- . Monoecism in *Juniperus scopulorum*. *Ibid.* 172. 1953.
- VASEK, F. C., & R. W. SCORA. Analysis of the oils of western North American junipers by gas-liquid chromatography. *Am. Jour. Bot.* **54**: 781–789. 1967. [*J. californica*, *J. deppeana*, *J. monosperma*, *J. occidentalis*, *J. osteosperma*, *J. scopulorum*.]
- VON RUDLOFF, E. Gas-liquid chromatography of terpenes. XVI. The volatile oil of the leaves of *Juniperus Ashei* Buchholz. *Canad. Jour. Chem.* **46**: 679–683. 1968.
- & F. M. COUCHMAN. The volatile oil of the leaves of *Juniperus scopulorum* Sarg. *Canad. Jour. Chem.* **42**: 1890–1895. 1964.
- ZANONI, T. A. The American junipers of the section *Sabina* (*Juniperus*, Cupressaceae)—a century later. *Phytologia* **38**: 433–455. 1978. [Synoptic taxonomic review of the group.]
- & R. P. ADAMS. The genus *Juniperus* (Cupressaceae) in Mexico and Guatemala: numerical and morphological analysis. *Bol. Soc. Bot. México* **35**: 69–92. 1975.
- & ———. The genus *Juniperus* (Cupressaceae) in Mexico and Guatemala: numerical and chemosystematic analysis. *Biochem. Syst. Ecol.* **4**: 147–158. 1976. [Species relationships based on terpenoid profiles.]
- & ———. The genus *Juniperus* (Cupressaceae) in Mexico and Guatemala: synonymy, key, and distributions of the taxa. *Bol. Soc. Bot. México* **38**: 83–121. 1979.
- ZIMMERMAN, H. E. A novel juniper tree. *Am. Bot.* **23**: 130. 1917. [A prostrate juniper ca. 0.5 m high and 40 m wide.]

5. *Callitris* Ventenat, Dec. Gen. Nov. 10. 1808.

Evergreen monoecious trees or shrubs with spreading or erect branches. Bark grayish, furrowed [brownish and fibrous in *C. Macleayana*]. Wood very dense, not distinctively colored. Juvenile leaves needlelike, in whorls of four; adult leaves scalelike, triangular, in whorls of 3, with bases decurrent and fused to the stem. Pollen cones solitary or clustered near branchlet tips; microsporangia in whorls of 3 [rarely 4], each with (2 or) 3 (or 4) sporangia. Ovulate cones globose [to ovoid or conical], terminal on short, thickened stalks, bearing 6 [sometimes 8 in *C. Macleayana*] cone scales in 2 alternating and unequal whorls of 3, appearing to form a single whorl at maturity; cone scales thickened, triangular-ovate, valvate and opening out from the very reduced cone axis (columella); ovules [6 to] 18 to 36 [to 54] per cone, in 3 intersecting rows arranged around the columella and at the base of the cone scales. Seeds flattened, irregularly tetrahedral, bearing [1 or] 2 or 3 lateral wings; cotyledons 2 (rarely 3). Chromosome number  $2n = 22$ . (Including *Octoclinis* F. Mueller; *Frenela* Mirbel.) LECTOTYPE SPECIES: *Callitris rhomboidea* (R. Br.) A. & L. Rich.; see Bullock, Taxon 6: 227. 1957. (From Greek *kallistos*, beautiful, and *treis*, three, in reference to the arrangement of leaves and cone scales.)—CYPRESS PINE.

A genus of approximately 15 species, 13 in Australia and two in New Caledonia. *Callitris* is divided into sect. OCTOCLINIS Bentham, including only *C. Macleayana* (F. Mueller) F. Mueller, and sect. CALLITRIS (sect. *Hexaclinis* Bentham). *Callitris Macleayana* is unusual in having some ovulate cones (those on shoots retaining the juvenile leaf type) with eight rather than six scales, both numbers often occurring on the same tree; loosely fibrous rather than dense, vertically furrowed bark; and only one elongate wing on the seed rather than two or three smaller ones (Baker & Smith; Clifford & Constantine; Garden).

*Callitris columellaris* F. Mueller var. *campestris* Silba (*C. glaucophylla* J. Thompson & L. Johnson; *C. glauca* R. Br. ex Baker & Smith, nom. illegit.), white cypress pine,  $2n = 22$ , has escaped from cultivation and has become locally naturalized in sand-pine (*Pinus clausa*) scrub in Brevard, Indian River, Orange, Osecola, and Seminole counties in eastern Florida (Judd, pers. comm.; Little, 1979; Wunderlin, pers. comm.). It is characterized by usually glaucous, unkeeled leaves and generally solitary ovulate cones with rugose but not verrucate scales that separate to near the base at maturity.

The nomenclature and species circumscription in the *Callitris columellaris* complex has been controversial. Franco chose a specimen referable to *C. columellaris* var. *columellaris* as a lectotype for *C. Hugelii*, a new combination based on *Frenela Hugelii* Carr., which would be an earlier name for the species. Blake has contended, however, that the specimen chosen was an inappropriate neotype probably representing a different species from that described in the protologue.

Several authors (Baker & Smith; Garden; Lacey; Thompson; Thompson & Johnson) have recognized three ecogeographic species in the *Callitris columellaris* complex: *C. glaucophylla* (*C. glauca*) in inland areas of the southern two thirds of Australia, *C. intratropica* Baker & Smith in the tropical zone of northern Australia, and *C. columellaris* s.s. in coastal areas of Queensland and

New South Wales. Other authors (Blake; Clifford & Constantine; Dallimore & Jackson; Venning, 1979, 1986) have emphasized morphological intergradation among these taxa, however, and they are treated here as varieties following Silba. There appear to be genetically based differences in plant habit and in foliage color and density among the three varieties (Lacey; Thompson & Johnson). In particular, the inland var. *campestris* usually has more glaucous foliage than the other varieties (hence the name "white cypress pine"), while var. *columellaris* has denser, dark green leaves and a more irregular branching pattern. Varieties *campestris* and *columellaris* are quite similar in cone size, while var. *intratropica* (Baker & Smith) Silba has been distinguished on the basis of its smaller cones (usually less than 1.8 cm wide) with narrower upper cone scales (Thompson & Johnson). It is uncertain whether plants from southern Queensland, between the generalized geographic ranges given for vars. *intratropica* and *campestris* by Thompson & Johnson, were included in the morphological comparisons (see Blake). Differences in leaf and wood chemistry among the taxa have been reported based on limited sampling (see Baker & Smith; Lacey; Thompson & Johnson), but thorough range-wide comparisons are needed to assess their validity.

The widespread south Australian species *Callitris Preissii* Miq. can also approach *C. columellaris* in morphology and leaf-oil chemistry (Adams & Simmons), and the taxa have been reported to produce fertile hybrids (Thompson & Johnson).

Chromosome counts for six species of *Callitris*, all  $2n = 22$ , were given by Mehra & Khoshoo. Similar karyotypes are seen in these species, with the chromosomes having median or submedian centromeres. Natural hybridization has been reported for three of these taxa, *C. Preissii*, *C. verrucosa* (A. Cunn. ex Endl.) F. Mueller, and *C. columellaris* var. *campestris*, in all possible combinations (Adams & Simmons; Garden; Thompson & Johnson).

Morphologically, *Callitris* shows the greatest similarity to the western Australian genus *Actinostrobus* Miq., which differs most prominently in having its ovulate cones subtended by a number of closely imbricate bracts. These are lacking in *Callitris*. Both genera have decurrent leaves in whorls of three and ovulate cones of six basally fused cone scales; they also have similar biflavonoid profiles, lacking in cupressuflavone and hinokiflavone derivatives (Gadek & Quinn, 1985). The southern African *Widdringtonia* Endl., which is similar to *Callitris* and *Actinostrobus* in embryology, differs in having decussately opposite foliage leaves, only four scales per ovulate cone, and a much more complex biflavonoid profile.

The sesquiterpene alcohol guaialol is a very characteristic component of the heartwood of *Callitris*, often crystallizing from cut stumps (Baker & Smith); within the Cupressaceae s.l. it has otherwise been reported only from the New Caledonian genus *Neocallitropsis* (H. Erdtman & Norin).

Several species of *Callitris* are important timber trees in Australia, furnishing hard, durable, termite-resistant wood for construction. The bark is rich in tannin. Resin exuding from the inner bark of cut stumps is similar to sandarac (obtained from *Tetraclinis*) and has been used in the manufacture of varnishes and incense (Lacey). In Australia various species of *Callitris* are widely planted

as windbreaks and ornamental trees and are particularly valuable for their drought resistance.

## REFERENCES:

- Under family references see CLIFFORD & CONSTANTINE; DALLIMORE & JACKSON; DOYLE & BRENNAN, 1972; H. ERDTMAN & NORIN; GADEK & QUINN, 1985; GAUSSEN, 1968; HARDIN; HART; HEGNAUER, 1962, 1986; KRÜSSMANN; LITTLE, 1979; MEHRA & KHOSHOO; and SILBA.
- ADAMS, R., & D. SIMMONS. A chemosystematic study of *Callitris* (Cupressaceae) in south-eastern Australia using volatile oils. *Austral. Forest Res.* **17**: 113-126. 1987. [*C. columellaris*, *C. Endlicheri*, *C. Preissii*, *C. rhomboidea*, *C. verrucosa*.]
- BAIRD, A. M. The life history of *Callitris*. *Phytomorphology* **3**: 258-284. 1953.
- BAKER, R. T., & H. G. SMITH. A research on the pines of Australia. xiv + 458 pp. 28 unnumbered pls., 3 maps. Sydney. 1910. [Extensive treatment of *Callitris*, 13-290, including morphology, chemistry, wood and leaf anatomy, and uses; excellent illustrations.]
- BLAKE, S. T. New or noteworthy plants chiefly from Queensland. *Proc. Roy. Soc. Queensland* **70**: 34-39. 1959. [*C. Hugelii* treated as a name of uncertain application.]
- BOLAND, D. J., coord. Forest trees of Australia, ed. 4. xvi + 687 pp. Melbourne. 1984. [*Callitris*, 48-56; *C. columellaris* (as *C. glauca*), *C. Macleayana*, *C. Preissii*; maps, photographs including SEM's of leaves and pollen cones.]
- BULLOCK, A. A. The typification of the generic name *Callitris* Vent. *Taxon* **6**: 227, 228. 1957. [*C. rhomboidea* proposed as lectotype species.]
- COSTERMANS, L. Native trees and shrubs of southeastern Australia. vi + 422 pp. Dee Why West, New South Wales. 1986. [*Callitris*, 142, 381; maps, illustrations of cones, photographs of habit.]
- FRANCO, J. DO A. Nomenclatura de algumas coníferas. *Anais Inst. Super. Agron.* **19**: 12-15. 1952. [*C. Hugelii* lectotypified as an earlier name for *C. columellaris*.]
- GARDEN, J. A revision of the genus *Callitris* Vent. *Contr. New S. Wales Natl. Herb.* **2**: 363-392. 1957.
- KHAN, I. U., & W. H. ANSARI. Flavonol glycosides from *Callitris glauca*. *Phytochemistry* **26**: 1221, 1222. 1987.
- LACEY, C. J. Silvicultural characteristics of white cypress pine. *Res. Note Forestry Commis. New S. Wales* **26**. 51 pp. 1973. [*C. glauca* = *C. columellaris*.]
- LOOBY, W. J., & J. DOYLE. New observations on the life history of *Callitris*. *Sci. Proc. Roy. Dublin Soc.* **22**: 241-255. 1940.
- RUDMAN, P. Causes of natural durability in timber. *Holzforschung* **18**: 52-57. 1964.\* [Chemistry of *Callitris* species.]
- SAXTON, W. T. Contributions to the life history of *Callitris*. *Ann. Bot.* **24**: 557-569. 1910.
- THOMPSON, J. Cupressaceae. *Contr. New S. Wales Natl. Herb., Flora Ser.* **1-18(5)**: 46-55. 1961.
- & L. A. S. JOHNSON. *Callitris glaucophylla*, Australia's "white cypress pine"—a new name for an old species. *Telopea* **2**: 731-736. 1986. [Replaces *C. glauca* when *C. columellaris* is treated as distinct.]
- VENNING, J. Character variation in Australian species of *Callitris* Vent. (Cupressaceae). Unpubl. Ph.D. dissertation, University of Adelaide. 1979.\* [Recognizes 13 species in Australia.]
- . *Callitris* Vent. Pp. 105-108 in J. JESSOP & H. R. TOELKEN, eds., *Flora of South Australia*, part I. ed. 4. Adelaide. 1986.